



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-153-20142-00-00

RECEIVED
STATE CORPORATION COMMISSION
NOV 9 1972
11-09-1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Leo Swords of Murfin Drilling Company has this

date requested permission to plug the following described well:

Mr. Swords guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Company,

Complete Address: 217 North Water Wichita, Kansas.

Lease Name: Elma Rogers Well No. 1-V

Location: CNE-SW Sec. 10 Twp. 3 Rge. (E)(W) 33

County: Rawlins Total Depth 4240' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Swords was instructed to plug the well as follows:

208' = 10 3/4" Surface casing, cement circulated with 200 Sx. (9" Hole).
Top of Dakota section @ 1800'.

Circulate hole with heavy mud. Pull DP to 2025' and displace 135 Cu. Ft. cement thru DP. Pull DP to 215' and displace 35 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 15 Cu. Ft. cement to bottom of cellar.

Very truly yours,

M. L. Nichols

Conservation Division Agent