



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-153-20053-00-00

RECEIVED
STATE CORPORATION COMMISSION
08-18-1969
AUG 18 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. John Scarbrough of Thomas Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Scarbrough guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company,

Complete Address: 812 Union Center Building, Wichita, Kansas.

Lease Name: Kogl Well No. 1

Location: SW-NE-NE Sec. 3 Twp. 3 Rge. (E)(W) 33

County: Rawlins Total Depth 4446 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Scarbrough was instructed to plug the well as follows:

220'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @1110'.

Circulate hole with heavy mud. Pull DP to 1365' and displace 100 Sx.
cement thru DP. Pull DP to 250' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

H. L. Nichols
Conservation Division Agent