



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

15-153-20166-00-00

RECEIVED STATE CORPORATION COMMISSION OCT 17 1973 10-17-1973 CONSERVATION DIVISION Wichita, Kansas

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. R. L. Sixbury of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Sixbury guarantees payment of the plugging fee.

Operator's full Name: Empire Drilling Company,

Complete Address: 650 Fourth National Bank Bldg., Wichita, Kansas.

Lease Name: Weishapl Well No. 1

Location: SW-SW-SW Sec. 25 Twp. 3 Rge. (E)(W) 34

County: Rawlins Total Depth 4195' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sixbury was instructed to plug the well as follows:

2 1/4" - 8 5/8" Surface casing, cement circulated with 175 Sx. Top of Dakota section @ 1675'.

Circulate hole with heavy mud. Pull DP to 1900' and displace 110 Cu. Ft. cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

H. L. Daniels Conservation Division Agent