

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-22697-00-00  
Spot: E2SWNE Sec/Twnshp/Rge: 21-15S-18W  
3300 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: ENGEL Well #: 6  
County: ELLIS Total Vertical Depth: 3680 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 4514 COLE AVE., STE 740, LB 30  
DALLAS, TX 75205

PROD Size: 5.5 feet: 3616 150 SX CMT  
SURF Size: 8.625 feet: 1140 400 SX CMT

\$ 119<sup>60</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/01/2004 8:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JOES MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Cut casing loose at 2250'.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/01/2004 11:00 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back casing to 3350' and topped with 5 sxs cement using a dump bailer.  
Cut casing loose at 2250'.  
Pulled up to 1850' - mixed and pumped 120 sxs cement with 300# hulls.  
Pulled up to 1200' - spotted 40 sxs cement with 100# hulls.  
Pulled up to 500' - spotted 30 sxs cement with 100# hulls.  
Pulled up to 200' and circulated cement with 40 sxs cement.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3436 | 3503 |      |          |

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed \_\_\_\_\_

*Jay Pfeifer*  
(TECHNICIAN)

INVOICED

DATE: 9-8-04

INV. NO. 2005060508

Form CP-2/3

SEP 03 2004

