

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-00132-00-00
Spot: NENESW Sec/Twnshp/Rge: 12-12S-23W
2310 feet from S Section Line, 3300 feet from E Section Line
Lease Name: NEWCOMBER Well #: 1
County: TREGO Total Vertical Depth: 4130 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

PROD Size: 5.5 feet: 4130
SURF Size: 8.625 feet: 205

134²³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/31/2004 12:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: RON NELSON Company: DOWNING-NELSON OIL Phone: (785) 628-3449

Proposed Plugging Method: Ordered out 280 sxs 60/40 pozmix - 10% gel - 500# hulls.
Fluid level 3900'.
No depth of 4 1/2" liner - no records.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/31/2004 1:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Allied pumped 200 sxs 60/40 pozmix - 10% gel with 500# hulls.
Blew hole in 4 1/2" below collar.
Braden head full of cement.

RECEIVED
SEP 08 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. EMERGENCY PLUG ORDER GIVEN.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE 9-8-04

INV. NO. 2005060505

SEP 03 2004

IMPERIAL OIL

#1 NEWCOMBER

12-12-23W

NE NE SW

Contr.

IMPERIAL OIL

TREGO

County

E. 2413^{RB} Comm.

2-28-56

Comp.

4-6-56

IP

3000 BOPD/LANS

Tops	Depth	Datum
ANH	1811	602
HEEB	3612	-1199
TOR	3630	-1217
LANS	3645	-1232
CONG	4065	-1652
ARB	4077	-1664
TD	4130	-1717

Casing
 8" 205 DST 3621-41/ 2 HR, 120' H
 OCM, BHP 1100#: DST 3641-56
 5" 4130 /1 HR, 570' OC SW, BHP 1130#
 DST 3678-99/1 HR, 1450' GAS, 450' OIL, BHP
 1150#: DST 3732-45/1 HR, 2400' OIL, BHP
 1210#: DST 3716-27/1 HR, 1020' OIL, BHP
 1145#: DST 3699-3710/1 HR, 2100' OIL, BHP
 1150#: DST 3742-56/1 HR, 120' OCM, 240'
 OIL, BHP 1235#: DST 3783-3809/1 HR, 34'
 MUD, BHP 115#: DST 3800-27/1 HR, 25' MUD
 BHP 65#: DST 3843-66/1/2 HR, 8' SL OCM, BHP
 750#: DST 3819-66/1/2 HR, 20' MUD, BHP 645#
 PERF 26/3733-36: SWB 10 BOPH/1 HR: ACID
 1700: SWB 70 BOPH/3 HR:

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

4301021