

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-24034-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 8-13S-19W  
330 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: SLAUGHTER A Well #: 1  
County: ELLIS Total Vertical Depth: 3800 feet

Operator License No.: 30717  
Op Name: DOWNING-NELSON OIL CO INC  
Address: PO BOX 372  
HAYS, KS 67601

PROD Size: 4.5 feet: 3799 225 SX CMT  
SURF Size: 8.625 feet: 511 280 SX CMT

\$123<sup>50</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/31/2004 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: RON NELSON Company: DOWNING-NELSON OIL Phone: (785) 628-3449

Proposed Plugging Method: Ordered out 215 sxs 60/40 pozmix - 10% gel - 500# hulls - 12 sxs gel spacer.  
Fluid level 3300'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/31/2004 11:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 40 sxs 60/40 pozmix - 10% gel with 100# hulls and 12 sxs gel spacer with 200# hulls.  
This was followed with 140 sxs 60/40 pozmix - 10% gel with 200# hulls.  
Max. P.S.I. 500#. S.I.P. 100#.  
Total 180 sxs cement with 12 sxs gel spacer.  
Hooked up to backside - instant 1000#.

Perfs:

Top	Bot	Thru	Comments
3723	3725		
3708	3720		
3492	3494		

Remarks: ALLIED CEMENTING COMPANY. EMERGENCY PLUG ORDERS GIVEN.

Plugged through: CSG

District: 04

10.

Signed

*Richard Williams*

(TECHNICIAN)

INVOICED

DATE

9-8-04

INV. NO.

2005060505

Form CP-2/3

SEP 03 2004


STAR OIL COMPANY  
 BOX 56  
 VICTORIA, KS 67671

#1 'A' SLAUGHTER  
 8-13-19W  
 SW SW SW

CONTR DREILING OIL, INC. CTY ELLIS

GEOL RON NELSON FIELD DISNEYLAND EXT (1/4 E)

ELV 2080 K B SPD 9/21/84 CARD ISSUED 2/28/85 IP P 6 BO & 17 BWPD  
 2075 GL MARM 3708-3725 OA



LOG	Tops	Depth/Datum
ANH	1424 +	656
B/ANH	1470 +	610
TOP	3140-1060	
HEEB	3379-1299	
TOR	3402-1322	
LANS	3422-1342	
BKC	3668-1588	
[7MARM	3704-1624	
PBTD	3799-1719	
RTD	3800-1720	

API 15-051-24,034

8 5/8 " 511 / 280SX, 4 1/2 " 3799 / 225SX

DST (1) 3696-3730 (MARM) / 45-45-45-45, REC 120' HOCM  
 (85% OIL) & 2' CL OIL, SIP 1007-929#, FP 39-49 / 59-69#

MICT - CO, PF (MARM) 3723-25 & 3708-20, W / 2 SPF, AC 750G  
 (7.5% MCA) SWB DWN, FRAC 255 SX SD & FRAC FL, SWB DWN,  
 SO, POP, P 6 BO & 17 BWPD, 10/6/84

COPYRIGHT 1984  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS

NOTICE  
 THIS IS A COPY OF THE ORIGINAL RECORD  
 OF THE WELL LOGS FOR THIS WELL  
 AND IS NOT TO BE USED FOR ANY OTHER PURPOSE  
 WITHOUT THE WRITTEN PERMISSION OF  
 INDEPENDENT OIL & GAS SERVICE, INC.