

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-00717-00-00  
Spot: W2SENW Sec/Twnshp/Rge: 2-11S-21W  
3300 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: COOK Well #: 4  
County: TREGO Total Vertical Depth: 3768 feet

Operator License No.: 9090  
Op Name: CHARTER ENERGY, INC.  
Address: PO BOX 252  
GREAT BEND, KS 67530

PROD Size: 5.5 feet: 3720  
SURF Size: 8.625 feet: 160

\$122<sup>46</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/01/2004 12:30 PM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: STEVE BAIZE Company: CHARTER ENERGY, INC. Phone: (620) 793-9090

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 600# hulls.  
Fluid level 200' - casing leak.  
DV tool at 1532' w/350 sxs.  
Squeezed 780' - 812' w/100 sxs.  
Set CIBP at 3500'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/01/2004 5:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

M.I.R.U. Ran tubing to 2200'.  
Allied pumped 125 sxs 60/40 pozmix - 10% gel with 200# hulls - circulated cement.  
PTOH. Allied squeezed with 200 sxs cement with 400# hulls.  
Max. P.S.I. 300#. S.I.P. 100#.  
Hooked up to backside. Instant pressure 500#.

Remarks: ALLIED CEMENTING COMPANY. EMERGENCY PLUG ORDERS GIVEN WHILE RIG OVER HOLE.

Plugged through: TBG

District: 04

10.

Signed

Richard Williams  
(TECHNICIAN)

INVOICED

DATE

9-8-04

INV. NO.

2005060504

Form CP-2/3

SEP 03 2004

PEEL-HARDMAN #4 COOK 2-11-21W  
W2 SE NW


Contr PEEL-HARDMAN TREGO County

E 2073 RE Comm. 1-30-55 Comp. 3-25-55 IP 51 BOPD  
PHY POT

Tops	Depth	Datum
ANH	1520	553
HEEB	3300	-1227
LANS	3345	-1272
ARB	3705	-1632
TD	3768	-1695

Casing  
8" 160  
5" 3720  
PERF 3564-68: ACID 500;  
PERF 3559-44: ACID 2000; WTR  
PB 3934: PERF 3525-29: ACID  
500

WHITE SW POOL



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS