

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-00737-00-00
Spot: NWSENW Sec/Twnshp/Rge: 2-11S-21W
3630 feet from S Section Line, 3630 feet from E Section Line
Lease Name: COOK Well #: 13
County: TREGO Total Vertical Depth: 3685 feet

Operator License No.: 9090
Op Name: CHARTER ENERGY, INC.
Address: PO BOX 252
GREAT BEND, KS 67530

PROD Size: 5.5 feet: 3680
SURF Size: 8.625 feet: 186

#119⁷⁶

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/01/2004 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: STEVE BAIZE Company: CHARTER ENERGY, INC. Phone: (620) 793-9090

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Fluid level 200'.
DV tool at 1563'.
Casing parted at 1400'.
Top of tubing fish 1446' - unable to get below 1446'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/01/2004 11:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1280'.
Allied pumped 50 sxs cement with 200# hulls, followed with 50 sxs neat - cement circulated.
PTOH. Allied squeezed with 150 sxs cement with 300# hulls.
Max. P.S.I. 1000#. S.I.P. 500#.
Hooked up to backside - instant 500#.

Perfs:

Top	Bot	Thru	Comments
2934	2965		Squeezed in 2000.
2898	2900		
951	973		
0	178		

Remarks: ALLIED CEMENTING COMPANY. EMERGENCY PLUG ORDERS GIVEN WHILE RIG OVER HOLE.

Plugged through: TBG

District: 04

AD.

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 9-8-04

INV. NO. 2005060504

Form CP-2/3

SEP 03 2004

PEEL-HARTMAN OIL #13 COOK

2-11-21W
NW SE NW

Contr. PEEL BROS TREGO County

E 2100 Comm. 9-29-57 Comp. 11-29-57 IP 118 BOPD/ARB
PHY POT

Tops	Depth	Datum
ARB	3660	-1560
TD	3685	-1585

Casing
8" 186
5" 3680

CO: ACID 3000: 12 BOPH

TRICO POOL

+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

14000000