

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-03076-00-01
Spot: SWSENW Sec/Twnshp/Rge: 20-16S-11W
2970 feet from S Section Line, 3630 feet from E Section Line
Lease Name: PETER SCHMITT Well #: 6
County: BARTON Total Vertical Depth: 3393 feet

Operator License No.: 4252
Op Name: KAHAN AND ASSOCIATES, INC
Address: PO BOX 700780
TULSA, OK 74170

CIBP Size: feet: 3273
PROD Size: 5.5 feet: 3393 200 SX CMT
SURF Size: 10.75 feet: 415 175 SX CMT
175 SX CMT

\$110²⁷

Well Type: EOR UIC Docket No: E26574.5 Date/Time to Plug: 09/02/2004 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JOHN KLUG Company: KAHAN AND ASSOCIATES, INC. Phone: (620) 793-2047

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Squeezed at 562' w/200 sxs.
Squeezed at 1256' w/160 sxs.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/03/2004 1:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Don Karst RIH with tubing to 2000'.
Allied rigged to tubing and pumped 140 sxs 60/40 pozmix with 350# hulls mixed in to circulate cement into pit.
Pulled tubing and tied onto 5 1/2" casing with a swedge and pumped 15 sxs cement with 150# hulls mixed in.
Max. P.S.I. 300#. S.I.P. 300#.
RIH with 2" tubing to 340' in 10 3/4" casing.
Pumped 80 sxs 60/40 pozmix to fill 10 3/4" casing to surface.
Hole standing full of cement.

Perfs:

Top	Bot	Thru	Comments
3032	3276		
2850	3261		

Remarks: ALLIED CEMENTING COMPANY-TICKET #17657.

Plugged through: TBG

District: 04

HD.

Signed

Patricia Staab

(TECHNICIAN)

INVOICED

DATE

9-8-04

INV. NO.

2005060507

SEP 07 2004

SINCLAIR PRAIRIE OIL

#6 P SCHMIDT

20-16-11W
SW SE NW

Contr.

BARTON County

E 1879

Comm. 2-18-46

Comp. 3-9-46


IP

125 BOPD

2% WTR

Tops	Depth	Datum
ANH	730	
DOUG	2968	
LANS	3036	
S CONG	3317	
SH CONG	3340	
ARB	3379	
TD	3393	

Casing
 10" 409
 5" 3393
 SO 3060-65: 3075-80: 3085-90
 17/3373-77: 2 BWPB: Plug
 3351: 16/3324-33: 1 BWPB &
 SSO: 24/3315-20: Swb 5 BOPB
 A/1000: Swb 7 BOPB/12 hr: NW
 PB 3350



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

RECEIVED
 SEP 08 2004
 KCC WICHITA