

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22934-00-00
Spot: NESESE Sec/Twnshp/Rge: 21-15S-18W
990 feet from S Section Line, 330 feet from E Section Line
Lease Name: ENGEL Well #: 8
County: ELLIS Total Vertical Depth: 3860 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE., STE 740, LB 30
DALLAS, TX 75205

PROD Size: 5.5 feet: 3700 150 SX CMT
SURF Size: 8.625 feet: 1144 400 SX CMT

125 45

Well Type: SWD UIC Docket No: D21127.0 Date/Time to Plug: 09/02/2004 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Cut casing loose at 2060'.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/02/2004 3:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back casing to 3650' and topped with 5 sxs cement using a dump bailer.
Cut casing loose at 2060'.
Pulled up to 1850' - mixed and pumped 120 sxs cement with 300# hulls.
Pulled up to 1200' - spotted 40 sxs cement with 100# hulls.
Pulled up to 500' - spotted 30 sxs cement with 100# hulls.
Pulled up to 200' and circulated cement with 40 sxs.

Perfs:

Top	Bot	Thru	Comments
3700	3860		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

140

Signed

Jay Pfeifer
(TECHNICIAN)

INVOICED

DATE

9-8-04

INV. NO.

2005060508

Form CP-2/3

SEP 03 2004