

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20130-00-00
Spot: E2E2SW Sec/Twnshp/Rge: 21-29S-34W
1320 feet from S Section Line, 2540 feet from W Section Line
Lease Name: RAY OV Well #: 6-21
County: HASKELL Total Vertical Depth: 3200 feet

Operator License No.: 4824 CIBP Size: feet: 2820 WITH 20 SX CMT
Op Name: PIONEER NATURAL RESOURCES USA. PROD Size: 5.5 feet: 3198 WITH 550 SX CMT
Address: 5205 N. O'CONNOR BLVD. SURF Size: 8.625 feet: 694 WITH 250 SX CMT
IRVING, TX 75039

\$104⁰⁰

Well Type: GAS UIC Docket No: Date/Time to Plug: 08/30/2004 2:30 PM

Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DAVID HIGBEE Company: PIONEER NATURAL RESOURCES Phone: (972) 444-9001

Proposed Plugging Method: CIBP @ 2820' WITH 2 SX CMT. PLUG AT 710' WITH 50 SX CMT. PLUG AT 400' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 08/31/2004 11:10 AM

KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

Perfs:

PBTD 3100'. SET CIBP @ 2820' WITH 2 SX CMT ON TOP. LOAD CASING WITH MUD. 1ST PLUG PULL TO 710'. LOAD HOLE WITH MUD & SPOT 50 SX CMT. 2ND PLUG PULL TO 350' & SPOT 30 SX CMT. 3RD PLUG PULL TO 40' & SPOT 15 SX CMT. STAYED FULL.


Top	Bot	Thru	Comments
3152	3174		
2854	2888		

RECEIVED
SEP 08 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 816' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

(TECHNICIAN)

INVOICED

DATE

9-8-04

NO. 00

2005760509