

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Davis Petroleum
Address: 7 SW 26 Ave, Great Bend, Kansas 67530
Phone: (620) 793-3051 Operator License #: 4656
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 7/22/04 6-16-04 ^{KCC BEN 9-8-04} (Date)
by: Michael Maier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-135-23411-00-01
Lease Name: Wesley
Well Number: 1
Spot Location (QQQQ): SW - SW - NE
2070 2310 Feet from North / South Section Line ^{KCC BEN 9-8-04}
2310 Feet from East / West Section Line
Sec. 36 Twp. 19 S. R. 25 East West
County: Ness
Date Well Completed: 1/31/90 12/27/2003 ^{KCC BEN 9-8-04}
Plugging Commenced: 7/22/04
Plugging Completed: 7/22/04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface		0	800'	8 5/8"	800'	0
Production		0	4422'	4 1/2"	4422'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Check Backside to 500# - OK, Plugged Hole - 1st Plug @ 4247' W/ 20 sx. w/ 100# hulls, 2nd Plug @ 1800' w/ 30 sx. w/ 100# hulls, 3rd Plug @ 800' w/ 60 sx., 4th Plug top off well down 4 1/2" Casing with 20 sx. By Allied Cementing Co., 7/22/04 @ 3:00 p.m.

Name of Plugging Contractor: L. D. DRILLING, INC. License #: 6039'
Address: 7 SW 26 Ave, Great Bend, KS 67530
Name of Party Responsible for Plugging Fees: Davis Petroleum, Inc.
State of Kansas County, Barton, ss.

RECEIVED
SEP 07 2004
KCC WICHITA

Bessie Dewerff (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Bessie Dewerff
(Address) 7 SW 26 Ave, Great Bend, KS 67530



SUBSCRIBED and SWORN TO before me this 03 day of September, 20 04
Rashell Patten My Commission Expires: 02-02-07
Notary Public Rashell Patten

Plains, Inc.

P.O. Box 346
Ness City, KS 67560
Phone 785-798-3995

WORKTICKET No 10923
NEW WELL
OLD WELL
RIG # 1 DATE 7-21-04

COMPANY Davis Petroleum JOB TYPE Tubing COMPLETE
ADDRESS _____ LEASE Wesley INCOMPLETE
CITY/STATE _____ SEC 36 TWP 19 WELL# 1
ZIP CODE _____ COUNTY Ness ANG 25
STATE Ks

POSITION	NAME	HRS	REVENUE	TRAVEL	NONREVENUE	TOTAL HRS	WKD
OPERATOR	Kevin Koerner	3 1/2				3 1/2	
DERRICKHAND	Victor Nawa	3 1/2				3 1/2	
FLOOR HAND	Clay Henderson	3 1/2				3 1/2	

JTS	PULLED	WELL EQUIPMENT	JTS	RAN
		POLISHED RODS		
		PONY RODS		
		RODS		
		RODS		
		RODS		
		PUMP / VALVES		
		PUPS		
		TUBING	137	2 3/8
		SN / BBL		
		ANCHOR / PACKER		
		OTHER		

DESCRIPTION OF WORK BEING PERFORMED

Drive to the location and rigged up. Got ready to run tubing. Talked the tubing going in, ran in 139 joints and tagged bottom. Layed 2 joints down, around 40' off bottom and shut down for the day.

RECEIVED
SEP 07 2004
KCC WICHITA

RIG W/2 MEN	<u>3 1/2</u>	HRS@	<u>145.00</u>	PER HOUR	TOTAL	<u>507.50</u>
TRAVEL TIME	<u>Fuel Surchage</u>	HRS@	<u>5%</u>	PER HOUR	TOTAL	<u>25.38</u>
SWAB CUPS NO.	SIZE	TYPE	PER EACH	TOTAL		
SWAB CUPS NO.	SIZE	TYPE	PER EACH	TOTAL		
OIL SAVER RUBBERS			PER EACH	TOTAL		
DOPE	<u>X</u>		PER EACH	<u>25.00</u>	TOTAL	<u>25.00</u>
TUBING TONGS	<u>X</u>				TOTAL	<u>75.00</u>
ROD TONGS					TOTAL	
REVERSE CIRC. & SWIVEL					TOTAL	
OUT OF TOWN					TOTAL	
MISC.					TOTAL	
X COMPANY REPRESENTATIVE		DATE			TOTAL	<u>637.88</u>

Plains, Inc.

P.O. Box 346
Ness City, KS 67560
Phone 785-798-3995

WORKTICKET No 10924
NEW WELL
OLD WELL
RIG # _____ DATE 7-22-04

COMPANY Davis Petroleum JOB TYPE Tubing COMPLETE
ADDRESS _____ LEASE Wesley INCOMPLETE
CITY/STATE _____ SEC 36 TWP 19 WELL# 1
ZIP CODE _____ COUNTY Ness ANG 25
STATE Ks

POSITION	NAME	HRS	REVENUE	TRAVEL	NONREVENUE	TOTAL HRS	WKD
OPERATOR	Kevin Koerner	6			2	8	
DERRICKHAND	Victor Nava	6			2	8	
FLOOR HAND	Joey Koerner	6			2	8	

JTS	PULLED	WELL EQUIPMENT	JTS	RAN
		POLISHED RODS		
		PONY RODS		
		RODS		
		RODS		
		RODS		
		PUMP / VALVES		
		PUPS		
137	2 ³ / ₁₈	TUBING		
		SN / BBL		
		ANCHOR/PACKER		
		OTHER		

DESCRIPTION OF WORK BEING PERFORMED

Drove to the location and got ready to pull tubing. Allied started cementing. Pulled out 79 joints (1800') and Allied cemented. Pulled out 33 joints (3472) and cemented again. Pulled the rest of the tubing out and cemented up to surface. Rigged down and moved off of the location.

RECEIVED

SEP 07 2004

Took 2 hrs off for rig break down

KCC WICHITA

RIG W/2 MEN	6	HRS@	145.00	PER HOUR	TOTAL	870.00
TRAVEL TIME	Fuel	EXCHARGE	5%	PER HOUR	TOTAL	43.50
SWAB CUPS No.	SIZE	TYPE	PER EACH	TOTAL		
SWAB CUPS No.	SIZE	TYPE	PER EACH	TOTAL		
OILSAVER RUBBERS			PER EACH	TOTAL		
_____			PER EACH	TOTAL		
TUBING TONGS	X			TOTAL		75.00
ROD TONGS				TOTAL		
REVERSE CIRC. & SWIVEL				TOTAL		
OUT OF TOWN				TOTAL		
Misc.	Solvent	3gal		TOTAL		7.50
X	COMPANY REPRESENTATIVE		DATE	TOTAL		996.00

ALLIED CEMENTING CO., INC. 13013

Federal Tax I.D.# ~~4~~

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Ness City

DATE <u>7-22-04</u>	SEC. <u>36</u>	TWP. <u>19</u>	RANGE <u>25</u>	CALLED OUT <u>5:00 AM</u>	ON LOCATION <u>8:00 AM</u>	JOB START <u>8:15 AM</u>	JOB FINISH <u>3:00 PM</u>
LEASE <u>Wesley</u>		WELL # <u>1</u>		LOCATION <u>Ness City 7 south, 7 west</u>		COUNTY <u>Ness</u>	STATE <u>Ka</u>
<input checked="" type="radio"/> OLD OR NEW (Circle one)				math into			

CONTRACTOR <u>Plains Well Service</u>	OWNER <u>L.D.</u>
TYPE OF JOB <u>Plug thru tubing</u>	
HOLE SIZE <u>4 1/2</u>	T.D. <u>4222'</u>
CASING SIZE <u>8 5/8</u>	DEPTH <u>800'</u>
TUBING SIZE <u>2"</u>	DEPTH <u>4247'</u>
DRILL PIPE	DEPTH
TOOL	DEPTH
PRES. MAX	MINIMUM
MEAS. LINE	SHOE JOINT
CEMENT LEFT IN CSG.	
PERFS.	
DISPLACEMENT	

CEMENT	AMOUNT ORDERED <u>300 ox 60/40 6% gel</u>
	<u>200# hulls on side</u>
	<u>used 130 ox cement</u>
COMMON <u>78</u>	@ <u>7.65</u> <u>596.70</u>
POZMIX <u>52</u>	@ <u>4.00</u> <u>208.00</u>
GEL <u>8</u>	@ <u>11.00</u> <u>88.00</u>
CHLORIDE	@
<u>Hulls 200# .2</u>	@ <u>20.00</u> <u>40.00</u>
	@
	@
	@
	@
	@
HANDLING <u>310</u>	@ <u>1.25</u> <u>387.50</u>
MILEAGE <u>14.310.5</u>	<u>217.00</u>
TOTAL <u>1537.20</u>	

EQUIPMENT	
<u>Ness</u>	
PUMP TRUCK CEMENTER <u>D. Drifling</u>	
# <u>224</u> HELPER <u>Sim Weighman</u>	
BULK TRUCK	
# <u>357</u> DRIVER <u>Steve Turley</u>	
BULK TRUCK	
#	DRIVER

REMARKS:

KCC saw all: Mike Maier
1st CK BK side to 500' O.K. -
1st Plug - 20 ox with 100# hulls - 4247'
2nd Plug - 30 ox - 1800' with 100# hulls
3rd Plug - circulate with 60 ox @ 800'
4th top off well down 4 1/2 with 20 ox

SERVICE RECEIVED

SEP 07 2004

DEPTH OF JOB <u>4247'</u>	KCC WICHITA <u>580.00</u>
PUMP TRUCK CHARGE	
EXTRA FOOTAGE	@
MILEAGE <u>14</u>	@ <u>4.00</u> <u>56.00</u>
PLUG	@
	@
	@
TOTAL <u>636.00</u>	

CHARGE TO: Davis Petroleum Inc.
 STREET 7 SW 26 Avenue
 CITY Cheate Bend STATE Kansas ZIP 67530

FLOAT EQUIPMENT

	@	
	@	
	@	
	@	
	@	
TOTAL <u>0</u>		

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Mike Kasselmann

MIKE KASSELMAN
 PRINTED NAME

Thank you!