

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Range Oil Company, Inc.
Address: 125 N. Market, Suite 1120 Wichita, KS 67202
Phone: (316) 265 - 6231 Operator License #: 5120
Type of Well: D & A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: _____ (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 017 - 20,865 - 06 - 00
Lease Name: Jacobs Farms
Well Number: 1
Spot Location (QQQQ): NW - SW - SW - NW
2140 Feet from North / South Section Line
100 Feet from East / West Section Line
Sec. 10 Twp. 20 S. R. 7 East West
County: Chase
Date Well Completed: 8-2-04
Plugging Commenced: 8-25-04
Plugging Completed: 8-27-04

KCC
Ben
9-8-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	210	none
				5 1/2	463	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

A bridge plug was set at 255 feet (above top perforations at 288 feet). United filled the casing from 255 feet to surface with 42 sacks of cement (60/40 poz with 4% gel). A metal plate was welded on top of 8 5/8" casing. None of the 5 1/2" production casing could be recovered because it had been cemented from 463' to surface.

Name of Plugging Contractor: Range Oil Company, Inc. United Cementing + Acid Co, Inc. License #: 5120 30437
Address: 125 N. Market, Suite 1120 Wichita, KS 67202

Name of Party Responsible for Plugging Fees: Range Oil Company, Inc.
State of Kansas County, Sedgwick, ss.


John M. Washburn (Employee of Operator) or (Operator) on above-described well being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) John M. Washburn
(Address) 125 N. Market, Suite 1120 Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 3rd day of September, 2004
David Jervis My Commission Expires: 8/14/08
Notary Public

RECEIVED
SEP 07 2004
KCC WICHITA

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202





United Cementing and Acid Co., Inc.

Oil Well Cementing & Acidizing
 (316) 321-4880 • 800-794-0187 • FAX (316) 321-4720
 2510 West 6th Street • El Dorado, KS 67042

SERVICE TICKET

✓5723

DATE 8-27-04

CHARGE TO Range Oil COUNTY Chase CITY _____

ADDRESS _____ CITY _____ ST _____ ZIP _____

LEASE & WELL NO. Jacobs Farms #1 CONTRACTOR _____

KIND OF JOB Old hole Plug SEC. _____ TWP. _____ RNG. _____

DIR. TO LOC. Flm Dale, 3 South, East Int. 10:15 NEW

Quantity	MATERIAL USED	Serv. Charge	
42.5x	60/40 por + 4% gel @4.90		675.00
2.5x	gel @9.79		205.00
3 hrs	Run & Pull 1-inch	\$90.00	19.40
			270.00
44.5x	BULK CHARGE		
60	BULK TRK. MILES <u>2.20</u>		43.12
60	PUMP TRK. MILES		916.31
			123.00
	PLUGS		
		<u>.0530</u> SALES TAX	75.93
		TOTAL	1508.10

T.D. _____

SIZE HOLE _____

MAX. PRESS. _____

PLUG DEPTH _____

PLUG USED _____

REMARKS: Ran 1" plastic pipe to 250 ft. Brake circulation, mixt

pump 42.5x 60/40 por + 4% gel to surface. Cement circulated

in collar.

CSG. SET AT _____ VOLUME _____

TBG SET AT _____ VOLUME _____

SIZE PIPE 5 1/2" casing

PKER DEPTH _____

TIME FINISHED 1:15

RECEIVED

SEP 07 2004

KCC WICHITA

NAME Phillip Malone P-10
 UNIT NO. _____
James Thomas #26
 CEMENTER OR TREATER

EQUIPMENT USED
 NAME Josh Creely B-7
 UNIT NO. _____
 OWNER'S REP.