

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-155-20060-00-00  
None

LEASE NAME Hill

WELL NUMBER 3

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

300 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 27 TWP. 23S RGE. 4 ~~XXXX~~(W)

COUNTY Reno

LEASE OPERATOR TGT Petroleum Corporation

ADDRESS 7570 W. 21st-Bldg. 1010-D, Wichita, Ks. 67205

PHONE# (316) 773-2266 OPERATORS LICENSE NO. 5118

Date Well Completed 5-28-68

Character of Well Oil

Plugging Commenced 6/22/04 <sup>22</sup> KCC

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7/1/04 <sup>6/23/04</sup> BKR <sup>9-8-04</sup>

The plugging proposal was approved on 10-2-03 (date)

by Mike Wilson (KCC District Agent's Name).

Is ACO-1 filed? NA If not, is well log attached? Yes

Producing Formation Miss. Osage Depth to Top 3307' Bottom 3391' T.D. 3391'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	583'	None
				4 1/2"	3388'	None

RECEIVED  
SEP 08 2004  
KCC WICHITA

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Spot 50 sx on btm. Pump 60 bbls. water/w/500# hulls. Perf. 325' and 635', 50 sx/w/40 Poz. Circulate between 4 1/2" and 8 5/8". Pump 50 sx @ 650'; pump 50 sx @ 635'; pump 150 sx @ 325'. Pump 25 sx down backside with 1".

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor TGT Petroleum Corp. License No. 5118

Address 7570 W. 21st-Bldg. 1010-D, Wichita, Ks. 67205

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: TGT Petroleum Corp.

STATE OF Kansas COUNTY OF Sedgwick, ss.

B. Lynn Herrington

(~~Explores or Operator~~) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed that the same are true and correct, so help me God.

(Signature) B. Lynn Herrington

B. Lynn Herrington

(Address) 7570 W. 21st-Bldg. 1010-D

Wichita, Ks. 67205



SUBSCRIBED AND SWORN TO before me this 7th day of September, 20 04

Judith K. Moser  
Notary Public

My Commission Expires: 5/17/05

