

15-153-20286-00-01

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 13-153-20,286A

LEASE NAME Cahoj

WELL NUMBER #1

SPOT LOCATION NE/4 NW/4

SEC. 28 TWP. 3S RGE. 36XXX or (W)

COUNTY Rawlins

Date Well Completed 12/14/79

Plugging Commenced 6/6/85

Plugging Completed 6/6/85

LEASE OPERATOR Clark-Cahoj

ADDRESS Box 13 McDonald, Kansas 67745

PHONE # (417) 326-4486 OPERATORS LICENSE NO. 7904

Character of Well oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hill City

Is ACO-1 filed? yes If not, is well log attached? _____

Producing formation L-KC "B" Depth to top 4268 bottom 4272 T.D. 4426

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
L-KC	oil&water	4268	72	4 1/2"	4397'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Down casing: 3 sacks hulls with 50 sacks 50/50 pozmix with 6% gel and 3% CaCl followed by 10 sacks gel followed by 25 sacks 50/50 pozmix, 6% gel & 3% CaCl followed by 10 sacks gel followed by 25 sacks 50/50 pozmix, 6% gel & 3% CaCl mixed with 1 sack hulls.
Down Backside: Pumped 100 sacks 50/50 pozmix, 6% gel & 3% CaCl.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sun Cementing License No. ?
Address Oakley, Kansas


RECEIVED
STATE CORPORATION COMMISSION

STATE OF Colorado COUNTY OF Denver, ss. JUL 01 1985

James Dillie (employee of operator) of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James Dillie

(Address) 4469 So. WINONA CT, DENVER, Colo. 80236



SUBSCRIBED AND SWORN TO before me this 25 day of June, 1985

Nancy L. Wright
Notary Public

My Commission Expires 12-12-88