

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-153-20,365-00-01

LEASE NAME Cahoj SWDW

WELL NUMBER 2

4620 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 28 TWP. 3S RGE. 36 (E) or (W)

COUNTY Rawlins

Date Well Completed _____

Plugging Commenced 8/11/97 1:30pm

Plugging Completed 8/11/97 2:45pm

10-3-97
57:21

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Philpott Oil & Gas Co., Inc.

ADDRESS P.O. Box 450 Atwood, Ks 67730

PHONE#(913) 626-3011 OPERATORS LICENSE NO. 3602

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/11/97 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Disposal
Producing Formation Cedar Hills Depth to Top 2920 Bottom 3046 T.D. 4340

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		GL	369	8 5/8	369	0
		GL	3156	4 1/2	3156	1192

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set
Shot casing off at 1192'. Pulled and laid down 5 jts. Mixed 50 sacks 60/40 poz w/10% gell and 2 sacks hulls. Displaced at 1000'. Pulled and laid down 17 joints. Mixed 40 sacks 60/40 poz w/10% gell and displaced at 350'. Pump plug, circulate cement. Laid down last 7 joints.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Northwest Well Service License No. 31664

Address 17509 Road 14, Ft. Morgan, Co 80201

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Philpott Oil & Gas Co., Inc.

STATE OF Kansas COUNTY OF Rawlins, ss.


Roger W. Philpott, President (Employee of Operator) or (Operator) o
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts
statements, and matters herein contained and the log of the above-described well as filed tha
the same are true and correct, so help me God.

(Signature) Roger W. Philpott

(Address) P.O. Box 450 Atwood, Ks 67730

SUBSCRIBED AND SWORN TO before me this 29th day of Sept, 19 97

J. L. Dixon
Notary Public



Commission Expires: 10-23-98