

RECEIVED
JUL 26 2004
KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 03320858 - 00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 9/16/92.

Well Operator: Comanche Resources, LLC KCC License #: 32384
Address: 6520 N. Western, Suite 300 City: Oklahoma City
(Owner / Company Name) (Operator's)

State: Oklahoma Zip Code: 73116 Contact Phone: (405) 755 - 5900

Lease: Bird Well #: 2-10 Sec. 10 Twp. 32 S. R. 19 East West

Spot Location / QQQQ: - SW - SW County: Comanche Co., KS

660' Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

660' Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # n/a ENHR Docket # n/a Other: n/a

Conductor Casing Size: n/a Set at: n/a Cemented with: n/a Sacks

Surface Casing Size: 8 5/8" Set at: 649' Cemented with: 200 Sacks

Production Casing Size: 5 1/2" Set at: 6246' Cemented with: 290 Sacks

List (ALL) Perforations and Bridgeplug Sets: 6166'-67', 6133'-34', 6117'-18', 6098'-99' and 5778'-80'

RBP @ 6148', RBP @ 6108', RBP @ 5823' and CIBP @ 5700'

Elevation: 2045' (G.L. / K.B.) T.D.: 6250' PBTD: 5695' Anhydrite Depth: n/a
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Setting of CIBP w/2 sks of cement

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? Well was drilled by Hallwood Petroleum and bought by Comanche Resources on 12/01/98

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Dennis Dye

Phone: (405) 368 - 5927

Address: 6520 N. Western, Suite 300 City / State: Oklahoma City, OK 73116

Plugging Contractor: North Star Well Services KCC License #: 33115
(Company Name) (Contractor's)

Address: P.O. Box 1749 Woodward, OK 73802 Phone: (580) 256 - 5644

Proposed Date and Hour of Plugging (if known?): Sept. 1, 2004

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 7/22/04 Authorized Operator / Agent: Dawnsmith
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

11/04

9/04

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Comanche Resources Company
6520 N. Western Ave., Suite 300
Oklahoma City, OK 73116

July 29, 2004

Re: BIRD #2-10
API 15-033-20858-00-01
SWSW 10-32S-19W, 660 FSL 660 FWL
COMANCHE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely


David P. Williams
Production Supervisor

COMANCHE RESOURCES CO
OKLA CITY OK 73120

WILDCAT

10-32S-19W
C SW SW

#2-10 BIRD OWWO

site 2-1/4 W OF COLDWATER KS	city: COMANCHE	API 15-033-20858
contr: BEST WELL SVC	field: WC (BIRD NORTH POOL	
geol: NONE	OPENER)	
fr	spd	drig
date 07/21/2003	date 12/28/1998	comp 12/28/1998
	card	last
	issued 07/21/2003	revised 07/21/2003

*		

.ELV: 2059 KB, 2045 GL LOG
tops.....depth/datum
PENN.....3413 -1354
TOP.....3738 -1679
TOR.....4300 -2241
DOUG.....4384 -2325
LANS.....4458 -2399
PBTD.....5100 -3041
MISS.....5140 -3081
KIND.....5692 -3633
VIOLA.....5776 -3717
SIMP SH.....6018 -3959
ARB.....6096 -4037
LTD OLD.....6204 -4145
RTD OLD.....6250 -4191

IP status
GAS, F 20 MCFGPD, NW, MARM 5034-5052 OA, 01/01/1999
 NOTE: CORR & INFO REL 2/14/94 - CORR GAS TST &
 STATUS: WAS GAS WELL - TIGHT HOLE; CORR 7/21/2003 -
 CORR RTD (WAS 6204)
 OLD INFO: OPERATOR WAS HALLWOOD PETROLEUM, 2
 BIRD, SPD 08/11/1992, 08/26/1992 13-3/8" 137 / 200 SX, 8-5/8"
 664 / 350 SX (ALT 1), 5-1/2" 6246 / 415 SX, GAS/OIL, COF
 2,460 MCFG & 15 BO & 19 BWP, MISS 5148-5202 OA,
 10/07/1992(CARD ISSUED 12/14/1992)
 CONTR: ALLEN DRILLING
 GEOL: JAMES SPELLMAN / JIM MUSGROVE

PROPERTY OF
 KS. CORP. COMMISSION
 (over)

COPYRIGHT 2003
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

COMANCHE RESOURCES CO
OKLA CITY OK 73120

#2-10 BIRD OWWO

PROPERTY OF
 KS. CORP. COMMISSION
 10-32S-19W
 C SW SW

COMMENT: ACTUAL STAKED ELEV IS 2058.5 KB
NO CORES

DST (1) 4930-5054 (MARM, PAW), / 30-45-60-120, (1ST OP) SB OFF BTM BKT/90 SEC, GTS/25", GA 69.5 MCFG AT 24#/25" & 30" THRU 3/4 INCH CK, (2ND OP) SB OFF BTM BKT/20 SEC, GA 69.5 MCFG AT 24#/5", 55.2 MCFG AT 15#/10", NO GA AT 0#/15" THRU 3/4 INCH CK, CHG CK SZ TO 1/2 INCH, GA 36.5 MCFG AT 35#/20", 41.6 MCFG AT 44#/25", 42.5 MCFG AT 46#/30", 43.4 MCFG AT 48#/35" & 40", 44.3 MCFG

AT 50#/45" & STAB 50", 55" & 60", REC 180' DM (SYS CHL 8000 PPM), REMARK: ALL PRESSURES ARE OFFICE READINGS ISIP 1608# FSIP 1761# IFP 81# -105# FFP 102# -111# IHP 2461# FHP 2412# BHT 130'

DST (2) 5146-5190 (MISS), / 30-45-60-120, (1ST OP) SB OFF BTM BKT/20 SEC, GTS/2", GA 953 MCFG AT 6#/5", 1036 MCFG AT 7#/10" & STAB 15", 20", 25" & 30" THRU 1.5 INCH CK, (2ND OP) SB OFF BTM BKT/5 SEC, GA 1036 MCFG AT 7#/5" & STAB AT 5" EA TST FROM 10" THRU 60", REC 180' DM (SYS CHL 8000 PPM), REMARK: ALL PRESSURES ARE OFFICE READINGS ISIP 1706# FSIP 1704# IFP 228# -165# FFP 213# -132# IHP 2610# FHP 2530# BHT 128'

DST (3) 5773-5785 (VIOLA), / 30-60-30-60, (1ST OP) WB, DIED/15", BUT TIGHT SPT AT 1150', (2ND OP) NB, REC 62' DM (SYS CHL 10,000 PPM), REMARK: ALL PRESSURES ARE OFFICE READINGS ISIP 1961# FSIP 1812# IFP 35# -35# FFP 66# -66# IHP 3007# FHP 2911# BHT 128'

continued

COMANCHE RESOURCES CO
OKLA CITY OK 73120

Card 2

10-32S-19W
C SW SW

#2-10 BIRD OWWO

DST (4) 6108-6135 (ARB), / 30-60-45-90, (1ST OP) SB OFF BTM BKT/90 SEC, (2ND OP) SB OFF BTM BKT/20 SEC, REC 4570' W (RW 0.18 OHMS AT 63.5 OHMS, REC CHL 54,000 PPM, SYS CHL 11,000 PPM), REMARK: ALL PRESSURES ARE OFFICE READINGS ISIP 2210# FSIP 2223# IFP 326# -1541# FFP 1589# -2131# IHP 3166# FHP 2890# BHT 132'

DST (5) 6140-6180 (ARB), HIT BRIDGE AT 850', WOULD NOT GO, MISRUN, REMARK: HP ARE OFFICE READINGS IHP 400# FHP 389#

TRGT ZN: ARB, PTD 6300 (ARB), MICT - CO, PF (ARB) 6098-6099, 6117-6118, 6133-6134, 6166-6167, W / 4 SPF, AC 13,300 GAL (28% FOAMED), NON-COMMERCIAL, PF (VIOLA) 5778-5780, W / 4-SPF, AC 13,300 GAL (20% FOAMED), NON-COMMERCIAL, SET PLUG AT 5695, PF (MISS) 5148-5157, 5162-5172, 5176-5190, 5198-5202, W / 2 SPF, AC 1500 GAL 915% FE), SO, SET 2-7/8" TBG AT 5124, PKR AT 5129, POP, P 15 BO & 19 BWP & GAS, 9/30/1992, SI/96 HRS, SITP 1324#, STATE TST: 4-PT EST OF 2460 MCFGPD, GOR 164,000:1, 10/7/1992

NEW INFO: FR 07/21/2003, REWORKED 12/28/1998 DC 12/28/1998 MICT - CO, SET CIBP AT 5100, PF (PAW) 5040-5052, W / 3 SPF, SWB DWN, SG, NAT, RE-PF (PAW) 5034-5046, W / 3 SPF, SWB DWN, SG, NAT, SET 2-3/8" TBG AT 5021, NO PKR, SI, IFF 20 MCFGPD, NW, RESUMED PROD 1/1/1999

PROPERTY OF
 KS. CORP. COMMISSION