

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
**Type or Print on this Form
Form must be Signed
All blanks must be Filled**

Lease Operator: Hartman Oil Co., Inc.
 Address: 12950 E. 13th St. - Wichita, Ks. 67230-1457
 Phone: (316) 636-2090 Operator License #: 30535
 Type of Well: Oil D & A Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 8-25-04 (Date)
 by: Richard Lacey - w/ KCC (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 055-21833-0000
 Lease Name: Ward
 Well Number: # 4
 Spot Location (QQQQ): E2 - SE - SW - SE *KCC BEM 9-304*
330 Feet from North / South Section Line
1400 Feet from East / West Section Line
 Sec. 16 Twp. 22S S. R. 33W East West
 County: FINNEY
 Date Well Completed: N/A
 Plugging Commenced: 8-25-04
 Plugging Completed: 8-25-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		surface	335'	8-5/8"	335'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Drill Pipe - stuck in hole - Lost circulation @ 4731' - unable to regain circulation - spot 40 bbl oil - Weatherford Serv - ran free point - shot (5) holes @ 4086' - unable to move Drill pipe or pump into - ran free point - shot (5) 1/4" holes @ 1954' - unable move or pump into Drill pipe - backed Drill pipe off @ 1686' - moved pipe 2' - drill pipe stuck in hole - broke circulation - unable to move drill pipe - As Per KCC - pump 400 szs 60-40 W/ 6 % Gel @ 1686' - ran temp survey - TOC @ 135' - top off 100' w/ 40 sx 60-40 6 % w/ 1" tbg

Name of Plugging Contractor: Abercombie RTD, Inc. & Allied Cementing Co. License #: 30684

Address: 12950 E 13th St. N - Wichita, Ks. 67230-1457

Name of Party Responsible for Plugging Fees: Hartman Oil Co.

State of Ks. County, Finney, ss.

S. T. Mitchell

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) S.T. Mitchell

(Address) 4550 W 9 Mi Rd - Finney Co., Ks. 67530

SUBSCRIBED and SWORN TO before me this 31st day of August, 20 04
Katherina A. Jones My Commission Expires: May 20, 2007
 Notary Public

**RECEIVED
SEP - 1 2004
KCC WICHITA**

bn