

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Kent Drilling Co.
Address: 1406 E 4th Ave. Garnett, KS. 66032
Phone: (785) 448-3262 Operator License #: 5820
Type of Well: AB Oilwell Docket #: N/A
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic. Other) (If SWD or ENHR)
The plugging proposal was approved on: 8-3-04 (Date)
by: Thomas J. Welsh (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Bush city Shoestring Depth to Top: 605 Bottom: 617 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-003-N/A 19278-00-00
Lease Name: MULKEY
Well Number: 18
Spot Location (QQQQ): NW-NW-SE
2145 Feet from North / South Section Line
2295 Feet from East / West Section Line
Sec. 7 Twp. 21 S. R. 21 East West
County: ANDERSON
Date Well Completed: N/A
Plugging Commenced: 8-3-04
Plugging Completed: 8-4-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)			
Formation	Content	From	To	Size	Pulled Out


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

607' of 2" set on 10 1/2" packer - with 18 sack cement - Ran 250' of 1" pipe outside 2" Eil to surface with cement - (Actual) Ran 525' of 3/4" pipe inside 2" pipe - ran 210' of 1" pipe outside 2" pipe - Pump 102 sack cement 2" pipe came up inside & outside 2" pipe - Pull 1 1/4" ON 8-4-04 - Tag cement inside @ 60' - outside 2" @ 100' - Pump 2 sack cement inside 2" and 28 sack cement outside 2" cement @ surface

Name of Plugging Contractor: Rogelo Kent - DBA R.J. Enterprises License #: 3728
Address: 1203 E 4th Ave. Garnett, KS. 66032

Name of Party Responsible for Plugging Fees: M.J. Kent
State of Kansas County, Anderson, ss.

M.J. Kent Owner (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) M.J. Kent
(Address) 1406 E 4th Ave. Garnett, KS 66032

SUBSCRIBED and SWORN TO before me this 30th day of August, 2004
Michelle Wilson My Commission Expires: 9-11-07
Notary Public