

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-03307-00-01  
Spot: SESWSW Sec/Twnshp/Rge: 16-15S-13W  
330 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: RUPPENTHAL Well #: 3  
County: RUSSELL Total Vertical Depth: 3440 feet

Operator License No.: 7383  
Op Name: BOLDING, GRADY CORPORATION  
Address: PO BOX 486  
ELLINWOOD, KS 67526

PROD Size: 5.5 feet: 3322 150 SX CMT  
SURF Size: 8.625 feet: 147 80 SX CMT

\$111<sup>80</sup>

Well Type: SWD UIC Docket No: D02190.0 Date/Time to Plug: 08/30/2004 10:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: GRADY BOLDING Company: BOLDING, GRADY CORPORATION Phone: (620) 564-2240

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 10% gel - 500# hulls.  
1957 - Squeezed 1120'-1130' w/150 sxs.  
Open hole. 19 seconds to fluids.  
Dakota 149' - 400'; Anhy. 845' - 865'; Salt 1265' - 1488'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/30/2004 10:45 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Allied rigged up to backside and pumped 20 sxs 60/40 pozmix with 200# P.I.P.  
Blew casing head packing out of well.  
Tied onto 5 1/2" casing with a swedge and pumped 255 sxs 60/40 pozmix with 500# hulls mixed in.  
Max. P.S.I. 450#. S.I.P. 100#.

RECEIVED  
SEP 02 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED

DATE

9.3.04

INV. NO.

2005060481

Form CP-2/3

AUG 31 2004

KEYES DRUG CO      16-15-13W  
 #3      RUPPENTHAL      SE SW SW

Contr.      RUSSELL      County

E 1874      Comm. 5-6-46      Comp. 6-5-46      IP 101 BOPD

Tops	Depth	Datum	Casing
ANHY	840		8" 147
TOP	2755		5" 3322
HEEB	2991		
LANS	3017		
ARB	3319	-1445	
TD	3327		

SSO 3321-27  
 A/2000, swb 1/2 BOPH & S W  
 Swb 32 BO/22 hrs N W


INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS