

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-01652-00-01
Spot: SWSESE Sec/Twnshp/Rge: 1-18S-10W
330 feet from S Section Line, 990 feet from E Section Line
Lease Name: HABIGER Well #: 1
County: RICE Total Vertical Depth: 3400 feet

Operator License No.: 31528
Op Name: KELSO, MIKE - OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

PROD Size: 4.5 feet: 3238 75 sxs cement
SURF Size: 8.625 feet: 200 165 sxs cement

\$110⁵⁰

Well Type: SWD UIC Docket No: D16278.0 Date/Time to Plug: 08/31/2004 2:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-7397

Proposed Plugging Method: See actual report.

**RECEIVED
KCC DISTRICT #2
SEP 1 - 2004
WICHITA, KS**

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 08/31/2004 5:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded open hole to 2800' and put 4 sacks of cement on top. Cut off 4-1/2" casing at 2013'. Pulled casing to 1250' and pumped 35 sacks of cement with 200 lbs of cotton hulls. Pulled casing to 900' and pumped 35 sacks of cement with 200 lbs of cotton hulls. Pulled casing to 250' and circulated cement to surface.

60/40 posmix with 4% gel.

Perfs:

**RECEIVED
KANSAS CORPORATION COMMISSION
SEP 02 2004
CONSERVATION DIVISION
WICHITA, KS**

Remarks: ALLIED CEMENT #17872

Plugged through: CSG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 9-3-04
INV. NO. 2005060485