

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-20926-00-00
Spot: S2NESW Sec/Twnshp/Rge: 4-20S-9W
1650 feet from S Section Line, 3300 feet from E Section Line
Lease Name: MCGLYNN Well #: 2
County: RICE Total Vertical Depth: 3246 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

PROD Size: 5.5 feet: 3242 125 SX CMT
SURF Size: 8.625 feet: 231 165 SX CMT

\$105⁵⁰

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/27/2004 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-7397

Proposed Plugging Method: See actual report.

RECEIVED
KCC DISTRICT #2
SEP 1 - 2004
WICHITA, KS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 08/27/2004 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 2900' and put 5 sacks of cement on top. Cut off 5-1/2" casing at 2217'. Pulled casing to 1300' and pumped 35 sacks of cement. Pulled casing to 850' and pumped 35 sacks of cement. Pulled casing to 280' and circulated cement to surface. Pumped 150 lbs of cotton hulls at 1300' and 150 lbs of cotton hulls at 850' with the cement.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
4			

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 02 2004
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND CEMENT #24624

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 9-3-04
INV. NO. 2005060480