

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-01756-00-00
Spot: S2S2SE Sec/Twnshp/Rge: 28-21S-13W
330 feet from S Section Line, 1320 feet from E Section Line
Lease Name: MORRISON Well #: 5
County: STAFFORD Total Vertical Depth: 3737 feet

Operator License No.: 6170
Op Name: GLOBE OPERATING, INC.
Address: PO BOX 12
GREAT BEND, KS 67530

PROD Size: 5.5 feet: 3731
SURF Size: 8.625 feet: 270

\$121⁴⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/25/2004 9:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 2800' & 5 SX CMT. RIPPED 5 1/2' @ 730'. PUMP 100 SX CMT AND CIRCULATE TO SURFACE.

Plugging Proposal Received By: RICHARD LACEY

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 08/25/2004 12:47 PM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

SANDED HOLE TO 2800' & 5 SX CMT WITH BAILER. RIPPED 5 1/2" @ 730'. RAN TUBING TO 700' & PUMPED 100 SX CMT. CIRCULATED CMT TO SURFACE UP 5 1/2" & 5 1/2" X 8 5/8". PULLED TUBING. TOPPED OFF WITH 35 SX CMT.


Top	Bot	Thru	Comments
3731	3737	OH	

RECEIVED
SEP - 1 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

INVOICE#

DATE

9-3-04

FILE NO.

2005060482

Form 278