

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-21833-00-00  
Spot: E2SESWSE Sec/Twnshp/Rge: 16-22S-33W  
330 feet from S Section Line, 1400 feet from E Section Line  
Lease Name: WARD Well #: 4  
County: FINNEY Total Vertical Depth: 4731 feet

Operator License No.: 30535  
Op Name: HARTMAN OIL CO., INC.  
Address: 12950 E. 13TH  
WICHITA, KS 67230

SURF Size: 8.625 feet: 335

76  
\$153

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/24/2004 3:00 PM

Plug Co. License No.: 30684 Plug Co. Name: ABERCROMBIE RTD, INC

Proposal Rcvd. from: STAN MITCHELL Company: HARTMAN OIL Phone: (316) 636-2090

Proposed Plugging Method: 1ST PLUG AT 1960' WITH 50 SX CMT. 2ND PLUG AT 1130' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 30 SX CMT. 4TH PLUG AT 360' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: PARTIAL

Date/Time Plugging Completed: 08/25/2004 5:00 AM

KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

Perfs:


DRILL PIPE & COLLERS STUCK @ 4731' TO 0'. BACKED OFF DRILL PIPE AT 1686'. PUMPED 400 SX OF 60/40 POZMIX 6% GEL DOWN DRILL PIPE. GOOD CIRCULATION BUT NO CMT TO SURFACE. TEMPRATURE LOG CMT TOP = 140'. RAN 1" PIPE 100' INSIDE 8 5/8" X 4 1/2" DRILL PIPE ANNULUS. CIRCULATED CMT TO SURFACE WITH 45 SX CMT. RAN 1" INSIDE 4 1/2" DRILL PIPE & CIRCULATED CMT WITH 5 SX.

RECEIVED  
SEP - 1 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: DP

District: 01



Signed \_\_\_\_\_

(TECHNICIAN)

INVOICE#

DATE 9-3-04

INV. NO. 2005060483

Form C-23