

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-20515-00-00  
Spot: NWSE Sec/Twnshp/Rge: 28-23S-31W  
1980 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: DECHANT Well #: 1  
County: FINNEY Total Vertical Depth: 4919 feet

Operator License No.: 3045  
Op Name: LANG, KENNETH R.  
Address: 301 W. BELLEVUE  
GARDEN CITY, KS 67846

CIBP Size: feet: 4600  
MSCC Size: feet: 1994 WITH 200 SX CMT  
PROD Size: 4.5 feet: 4916 WITH 100 SX CMT  
SURF Size: 8.625 feet: 412 WITH 315 SX CMT

\$ 159<sup>87</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/26/2004 10:30 AM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: RUN IN HOLE WITH TUBING. SPOT 30 SX CMT AT 1300' INSIDE 4 1/2". CIRCULATE CMT. PULL OUT OF HOLE TO 430' & SPOT 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/27/2004 2:30 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PORT COLLAR @ 1994' WITH 200 SX CMT. CIBP @ 4600'. CASING TESTED GOOD TO 1500' WITH PACKER. 1ST PLUG RUN IN HOLE WITH TUBING TO 1300'. PUMP 30 SX CMT INSIDE 4 1/2" CASING. PULL OUT OF HOLE WITH TUBING. SDON. PULL STRETCH. SHOOT OFF AT 690'. 2ND PLUG PULL OUT OF HOLE TO 430'. LOAD HOLE & PUMP 50 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4852	4862		

RECEIVED  
SEP 02 2004  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 690' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED  
AUG 31 2004  
KCC Dodge City

Signed

Jim Holland  
(TECHNICIAN)

INVOICE  
DATE 8.3.04  
INV. NO. 2005060486

Form CP 3/3