

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-23825-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 22-24S-17E
3135 feet from S Section Line, 2155 feet from E Section Line
Lease Name: PAUL SICKA Well #: 2
County: WOODSON Total Vertical Depth: 1100 feet

Operator License No.: 32710
Op Name: LAYMON OIL II, LLC
Address: 1998 SQUIRREL RD
NEOSHO FALLS, KS 66758

PROD Size: 4.5 feet: 1100
SURF Size: 7 feet: 60

#3575

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/19/2004 8:00 AM
Plug Co. License No.: 8469 Plug Co. Name: NICKELL, RALPH DBA NICKELL DRILLING
Proposal Rcvd. from: KENNETH LAYMON Company: LAYMON OIL II, LLC Phone: (620) 963-2495

Proposed Plugging Method: THIS WELL CONSISTED OF 4.5" CASING TO 1100' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO PLACE A 50' PLUG AT T.D., A 50' CEMENT PLUG AT 500', AND TO PLACE A CONTINUOUS CEMENT PLUG FROM BOTTOM TO TOP.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: PARTIAL
Date/Time Plugging Completed: 08/23/2004 12:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

PLASTIC PIPE WAS RAN FROM A SPOOL TO 900'. 10 SACKS OF CEMENT WERE PUMPED THROUGH THE PIPE TO 900'. THE PIPE WAS PULLED TO 500' AND 5 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE PIPE WAS PULLED TO 250' CEMENT WAS PUMPED INTO THE PIPE UNTIL CEMENT CIRCULATED FROM THE 4.5" CASING AT SURFACE. THE PLASTIC PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. FALL BACK WAS REFILLED ON 08/23/04.

RECEIVED
SEP - 1 2004
KCC WICHITA

RECEIVED
KCC DISTRICT #3
AUG 25 2004 CPT
CHANUTE, KS

Remarks: THIS WELL IS LOCATED APPROX. 495' N. AND E. OF THE SW CORNER OF THE NE 1/4.

Plugged through: TBG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

INVOICED

DATE

9.3.04

INV. NO.

2005060488