

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-22434-00-00
Spot: W2SENE Sec/Twnshp/Rge: 21-15S-18W
3300 feet from S Section Line, 990 feet from E Section Line
Lease Name: ENGEL Well #: 5
County: ELLIS Total Vertical Depth: 3630 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE., STE 740, LB 30
DALLAS, TX 75205

PROD Size: 5.5 feet: 3630 150 SX CMT
SURF Size: 8.625 feet: 1172 425 SX CMT

#117⁹⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/30/2004 3:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.
Cut casing loose at 2280'.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/30/2004 5:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Sanded back casing to 3250' and topped with 5 sxs cement using a dump bailer.
Cut casing loose at 2280'.
Pulled up to 1850' - mixed and pumped 120 sxs cement with 300# hulls.
Pulled up to 1175' - spotted 40 sxs cement with 100# hulls.
Pulled up to 500' - spotted 30 sxs cement with 100# hulls.
Pulled up to 200' and circulated cement with 40 sxs cement.

Top	Bot	Thru	Comments
3313	3581		

RECEIVED
SEP 02 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

100

Signed _____

Jay Pfeifer

(TECHNICIAN)

INVOICED

DATE

9.3.04

INV. NO.

2005060489

Form CP-2/3

AUG 31 2004

R A COMEAU
 308 W MILL #5 ENGLE 21-15-18W
 PLAINVILLE, KS 67663 C W/2 SE NE
 CONTR PIONEER DRILG CO INC CTY ELLIS

GEOL _____ FIELD SCHOENCHEN

E 2012 KB CM 4/25/81 CARD ISSUED 8/13/81 IP P 48 BOPD & 120

API 15-051-22,434 BWPD
 ARB 3576-3581

+	+	+
+	+	+
+	+	+

SMP	TOPS	DEPTH	DATUM
IQP	2971	- 959	
HEEB	3237	-1225	
TOR	3258	-1246	
LKC	3288	-1276	
B KC	3512	-1500	
ERO ARB	3574	-1562	
ARB	3584	-1572	
RTD	3630	-1618	

8 5/8" 1172/425sx; 5 1/2" 3630/150sx
 NO DSTS
 MICT - CO, PF (ARB) 10/3576-3581, AC
 250G, SWB LD, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

MADE IN U.S.A.
 MADE IN U.S.A.
 MADE IN U.S.A.