

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20183-00-00
Spot: NENW Sec/Twnshp/Rge: 34-20S-33W
660 feet from N Section Line, 1980 feet from W Section Line
Lease Name: E J BAKER Well #: 1
County: SCOTT Total Vertical Depth: 5009 feet

Operator License No.: 3045
Op Name: LANG, KENNETH R.
Address: 301 W. BELLEVUE
GARDEN CITY, KS 67846

PROD Size: 4.5 feet: 2788 WITH 325 SX CMT
SURF Size: 8.625 feet: 601 WITH 400 SX CMT

\$162⁷⁹

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/24/2004 10:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: RUN PACKER ON TUBING TO 1250'. TEST CASING TO 300#. PULL TUBING & PACKER OUT OF HOLE. SPOT 20 SX CMT. PERFORATE AT 1250'. PUMP 80 SX CMT. PULL TO 630' & SPOT 50 SX CMT. PULL TO 300' & SPOT 30 SX CMT. PULL TO 40' & SPOT 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/25/2004 5:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PERFS SANDED IN TO 1600'. TEST CASING TO 1250' WITH TUBING & PACKER. TESTED GOOD. SPOT 20 SX CMT AT 1250' THROUGH TUBING. PERFORATE AT 1200'. SDON. ESTABLISH PUMPING RATE & PUMP 80 SX CMT. DISPLACE WITH MUD & SQUEEZE AT 1200'. SHUT IN AT 300#. LET SET FOR 1 HOUR. SHOOT CASING AT 700'. PULL OUT OF HOLE TO 640'. CIRCULATE HOLE WITH MUD & PUMP 50 SX CMT. GOOD CIRCULATION. PULL OUT OF HOLE TO 40'. LOAD HOLE & PUMP 10 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2696	2717		

RECEIVED
SEP 02 2004
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 700' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

RECEIVED
AUG 31 2004
KCC Dodge City

Signed

Jim Holland PART II
(TECHNICIAN)

INVOICED
DATE 9-3-04
INV. NO. 20050160486

Form CH-23