

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-023-20147-00-00

LEASE NAME Witham

WELL NUMBER 1-13

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 13 TWP. 3S RGE. 39 ~~4E~~or(W)

COUNTY Cheyenne

Date Well Completed 11-17-80

Plugging Commenced 9-27-87

Plugging Completed 10-14-87

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Barfield Oil Corporation

ADDRESS 1512 Larimer Street, #400 Denver, CO 80202

PHONE# (303) 572-3743 OPERATORS LICENSE NO. 4526

Character of Well Gas (ST)

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-28-87 (date)

by Shari Feist (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached?

Producing Formation Niobrara Depth to Top 1361' Bottom 1401' T.D. 1519'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Niobrara	Gas	0	301	7"	301'	0'
		0	1519	4½"	1519'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
*Please see back

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B-J Titan Company License No.

Address P.O. Box 200416 Houston, Texas 77216

STATE OF Colorado COUNTY OF Denver, ss.

Norman Nuss (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Norman Nuss

(Address) 1512 Larimer St., #400 Denver, CO 80202

SUBSCRIBED AND SWORN TO before me this 7th day of December, 1987

*Originally signed the 18th of November

Bonnie L. Allen
Notary Public

My Commission Expires: June 30, 1991

RECEIVED
STATE CORPORATION COMMISSION

DEC 10 1987

CONSERVATION DIVISION
Wichita, Kansas

12-10-87

The well was plugged in two stages. Initially on 9-27-87; well was plugged using 2 sx hulls, 2 sx hulls with initial cement, finally lite cement. Cemented to surface in 4 $\frac{1}{2}$ " casing. No pipe was pulled. Annulus between surface pipe and casing filled with cement. Total of 60 sx cement. On 10-14-87 pumped additional 15 sx into casing. Pipe was cut 4' below ground and plate welded on top. Both days were witnessed by Mr. Carl Goodrow.

