

15-023-20069-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Cheyenne County, Sec. 4 Twp. 3S Rge. 37 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
330' FSL-990' FWL

Lease Owner Cities Service Company
Lease Name Dorsch "A" Well No. #1
Office Address 209 E. William, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed July 12 1978
Application for plugging filed March 14 1979
Application for plugging approved March 15 1979
Plugging commenced April 27 1979
Plugging completed April 29 1979

Reason for abandonment of well or producing formation
Uneconomical to produce

If a producing well is abandoned, date of last production
Well did not produce 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazar
Producing formation ----- Depth to top 4360' Bottom 4579' Total Depth of Well 5310'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	371'	None
				4-1/2"	4628'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set. Set bridge plug at 1380'.

HOWCO pumped into 4-1/2" casing - 20 sacks 50/50 Pozmix + 6% gel, 8 sacks gel, 4-1/2" plug, 15 sacks 50/50 Pozmix + 6% gel. Shut in @ 1800 psi, dropped to 300 psi.

RECEIVED
STATE CORPORATION COMMISSION

MAY - 7 1979

5-7-79

CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Company

STATE OF Kansas COUNTY OF Sedgwick, ss.

E. W. Peterman (employee of owner) or (operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) E. W. Peterman E. W. Peterman
209 E. William, Wichita, Kansas 67202

(Address)

before me this 3rd day of May, 1979

Glenn E. Meier
Glenn E. Meier Notary Public.

My commission expires 6-3-81

DRILLER'S LOG

15-023-20069-00-00

COMPANY: Cities Service Company

SEC. 4 T. 3S R. 37W

LOC. SE SW SW

WELL NAME: Dorsch "A" #1

COUNTY: Cheyenne

RIG NO. #1

TOTAL DEPTH 5310'

ELEVATION

COMMENCED: 6-29-78

COMPLETED: 7-12-78

CONTRACTOR: Rains & Williamson Oil Co., Inc.

CASING RECORD:

SURFACE: 8 5/8" @ 379' w/300 sx. Class A, 2% cc.

PRODUCTION: 4 1/2" @ 4708' w/300 sx. Lite and 15 sx. 50/50 poz., 10% salt, 3/4 of 1% CFR2, and 200 sx. Lite, 6% salt, 3/4 of 1% CFR2 and LOG 100 sx. 50/50 poz., 10% salt, 3/4 of 1% CFR2.

(Figures Indicate Bottom of Formations)

Sand & Shale	760
Shale	1428
Shale & Sand	2840
Sand & Shale	3059
Shale	3403
Shale, Sand & Lime	3544
Shale & Lime	3823
Lime & Shale	4536
Lime	4580
Lime & Shale	4776
Lime	4790
Lime & Shale	5284
Lime	5310
<u>ROTARY TOTAL DEPTH</u>	<u>5310</u>

RECEIVED
STATE CORPORATION COMMISSION

MAR 15 1979

CONSERVATION DIVISION
Wichita, Kansas

3-15-79

STATE OF Kansas)

COUNTY OF Sedgwick)

SS:

I, Wilson Rains, President of Rains & Williamson Oil Co., Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the

Dorsch "A" #1 well.

Wilson Rains

Wilson Rains

Subscribed and sworn to before me this 17 day of July, 1978.

My Appointment Expires:

10-4-79

Juanita M. Green
Juanita M. Green

