

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-153-20569-000

LEASE NAME Fisher

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 7-335

SPOT LOCATION C, NE, SE

SEC. 33 TWP. 3 RGE. 36 (W) (W)

COUNTY Rawlins

Date Well Completed 8-30-84

Plugging Commenced 8-30-84

Plugging Completed 8-30-84

LEASE OPERATOR Coastal Oil & Gas Corporation

ADDRESS Box 1332 Amarillo, Tx. 79189

PHONE # (806) 372-8121 OPERATORS LICENSE NO. 6593

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? KCC

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation Cherokee Depth to top 4629 bottom 4649 T.D. 4700'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Cherokee	Poor Show	0	395	8-5/8	395'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Fill hole with mud 1st Cement plug from 3060' to 2980' w/25 sks. 50/50 Poz 6% gel 3% CC. Fill hole with mud 2nd cement plug 2330' to 2030' w/100 sks. 50/50 poz 6% gel 3% CC. Fill hole with mud, 3rd cement plug from 420' to 300' w/40 sks. 50/50 poz 6% gel 3% CC. Fill hole with mud 4th cement plug from 40' to 0' w/10 sks. 50/50 poz 6% gel 3% CC. Filled rat hole w/10 sks. 50/50 poz 6% gel 3% CC.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. _____

Address Wichita, Kansas

STATE OF _____ COUNTY OF _____, ss. _____

RECEIVED
STATE CORPORATION COMMISSION

James E. Adams (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says:
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

SEP 21 1984

9-21-84

CONSERVATION DIVISION
WICHITA, KANSAS

(Signature) James E. Adams 79189

(Address) Box 1332 Amarillo Tx.

SUBSCRIBED AND SWORN TO before me this 19 day of September, 1984

M. R. [Signature]
Notary Public

My Commission expires: 11-12-85