

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market - Room 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-081-20130-0000

LEASE NAME RAY, OV

WELL NUMBER 6-21

1320' FSL Ft. from S Section Line

2540' FWL Ft. from E Section Line

SEC. 21 TWP. 29S RGE. 34W (E) or (W)

COUNTY HASKELL

Date Well Completed 8/28/04 *KCC BEN 9-10-04*

Plugging Commenced 8/30/04

Plugging Completed 8/31/04

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to GORS. Div.  
office within 30 days

LEASE OPERATOR PIONEER NATURAL RESOURCES USA, INC.

ADDRESS 5205 N. O'CONNOR BLVD., ROOM 1325 - IRVING, TX 75039

PHONE # (727) 444-9001 OPERATORS LICENSE NO. 4824

Character of Well GAS

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/03/04 *KCC BEN 9-10-04* (date)

by DAVID WILLIAMS (KCC District Agent's Name).

is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation COUNCIL GROVE Depth to Top 2990' KB Bottom 3100' T.D. 3200'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
COUNCIL GROVE	GAS	2854'	3174'	8 5/8"	694'	0
				5-1/2"	3198'	710'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set

8/31/04 P&A Operations witnessed by Gary Winters, KCC. POOH tbq, rods, subs. Set CIBP @ 2840'KB, spot 2 sx cmt @ 2820'KB. Revise PBD 2820'. Pmp 70 bbl 9 ppg 36 cp mud, cut 5 1/2' csq @ 710' pmp 20 bbl 9 ppg 36 cp mud circ. Spot 30 sx cmt plug 710'-560'+13 bbl 36 cp mud. Spot 30 sx cmt plug 350'-250'+5 bbl 9 ppg 36 cp mud. Spot 10 sx cmt plug 40'-surface. Cut off 8 5/8' csq 3' BGL, weld trash cover ID plate. RDMO.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

Address RT. 1, BOX 49BA TYRONE OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PIONEER NATURAL RESOURCES USA, INC.

STATE OF TEXAS COUNTY OF DALLAS, ss.

LINDA KELLY (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


RECEIVED

SEP 09 2004

KCC WICHITA

(Signature) Linda Kelly

(Address) 5205 N. O'CONNOR BLVD. RM 1325 IRVING TX 75039



SUBSCRIBED AND SWORN TO before me this 7TH day of SEPTEMBER, 20 04

My Commission Expires: 5/21/2005 Notary Public