

**Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

Form CP-4  
September 2003  
**Type or Print on this Form  
Form must be Signed  
All blanks must be Filled**

Lease Operator: NOBLE ENERGY, INC.  
 Address: 100 GLENBOROUGH, #100, HOUSTON, TX 77067  
 Phone: (281) 872-3100 Operator License #: 33190  
 Type of Well: D&A Docket #: \_\_\_\_\_  
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
 The plugging proposal was approved on: 10/06/2003 (Date)  
 by: \_\_\_\_\_ (KCC District Agent's Name)  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (If needed attach another sheet)  
NIORRARA Depth to Top: 1487 Bottom: 1508 T.D. 1682  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-023-20500-00 - 00  
 Lease Name: ZWEYGARDT  
 Well Number: 32-32  
 Spot Location (QQQQ): S - W - N - E  
1980 Feet from  North /  South Section Line  
1980 Feet from  East /  West Section Line  
 Sec. 32 Twp. 3 S. R. 41  East  West  
 County: CHEYENNE  
 Date Well Completed: 10/06/2003  
 Plugging Commenced: 10/06/2003  
 Plugging Completed: 10/06/2003

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
NIORRARA	GAS & WATER	1487	1508	7"	308'	0'

**RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 28 2003**

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in producing it into the hole. If cement or other plugs were used, state the character of same depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

PLUGGED WELL W/60:40 POZ MIX CEMENT W/6% GEL AS FOLLOWS: 100 SX CMT @ 1364', 40 SX CMT 1/2 IN & 1/2 OUT OF BOTTOM OF SURFACE CSG (CSG SET @ 314') AND 10 SX CMT @ TOP OF SURFACE. CUT OFF CSG 4' BELOW SURFACE. Plug #1 from 1364' - 550' (814'), Plug #2 from 476'-166' (310') and Plug #3 from 79'-4' (75')

Name of Plugging Contractor: EXCELL DRILLING COMPANY License #: 28085 8273  
 Address: P.O. BOX 305, WRAY, CO 80758-0305

Name of Party Responsible for Plugging Fees: NOBLE ENERGY, INC.  
 State of TEXAS County, HARRIS, ss.

PATRICIA JAENECKE, REGULATORY SPECIALIST III (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Patricia Jaenecke

(Address) 100 GLENBOROUGH, #100, HOUSTON, TX 77067



**PATSY J. NEVILL**  
 NOTARY PUBLIC STATE OF TEXAS  
 MY COMMISSION EXPIRES  
NOV 28 2004  
 I SUBSCRIBED AND SIGNED before me this 27<sup>th</sup> day of October, 2003  
J. Nevill My Commission Expires: 11-28-04  
 Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202 B



**CEMENTER'S WELL SERVICE, INC.**  
 P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE  
**183492**

*Noble*

Date <b>10-06-03</b>	Well Owner <b>Energy Inc.</b>	Well No. <b>32-37</b>	Lease <b>Zuliygard T</b>
County <b>Cheyenne</b>	State <b>Kansas</b>	Field	
Charge to <b>Excell Drilling Company</b>	Address <b>R. # 2</b>		Charge Code
City, State <b>Wray, Colorado, 80758</b>	Pump Truck No. <b>1204</b> Code		For Office Use Only
	Bulk Truck No. <b>1211</b> Code		
Type of Job	Depth	Ft.	To
Surface	Bottom of Surface	Ft.	To
Plug <b>3 1/2" D.P</b>	Plug Landed @	Ft.	Time On <b>02:00</b>
Production	Pipe Landed @	Ft.	Time Off <b>04:45</b>

Reference No.	Description	Qty.	Meas.	Unit Price	Amount
	Pump Truck Charge				
	Cement Neat <b>*</b>				
	Poz. Mix <b>✓ 60/40</b>	<b>150</b>	<b>SKS</b>		
	Calcium Chloride				
	Gel <b>6 %</b> Flo-Cele <b>1/4</b> #Per Sack				
	Handling Charge				
	Hauling Charge				
	Additional Cement				
	<i>1st plug @ 1364' w/ 100 SKS</i>				
	<i>2nd plug @ 280 1/2 in 1/2 out of surface casing w/ 40 SKS</i>				
	<i>2nd plug @ Top of surface casing w/ 10 SKS</i>				
	<i>Mixing Rate 4BPM - Displacement Rate 6BPM</i>				
	<i>Slurry Vol. 1.18 CU FT/sk - Slurry wt 15.2 PPG</i>				

RECEIVED  
 KANSAS CORPORATION COMMISSION  
 OCT 28 2003  
 CONSERVATION DIVISION  
 WICHITA, KS

Remarks:	Tax Reference Code	Sub Total
	<b>KS.4.9 %</b>	Tax
	Disc.	Total

  

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<b>1204</b>	Pump Truck			<b>40</b>		<b>15</b>	
<b>1211</b>	Bulk Truck			<b>40</b>		<b>15</b>	

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **Leon, John, Randy**

Received By **[Signature]**  
 Customer or His Agent