

15-023-20169-00-00

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Cheyenne SEC. 23 TWP. 3S RGE. 41 E/W  
 Location as in quarters or footage from lines:  
1980' FWL - 660' FNL

		23	

Locate Well  
 correctly on above  
 Section Platt.

Lease Owner Cities Service Company  
 Lease Name Zweygardt "A" Well No. 1  
 Office Address 209 E. William, Wichita, Kansas 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole): Gas  
 Date Well Completed February 27, 1981  
 Application for plugging filed March 29, 1982  
 Plugging commenced June 24, 1982  
 Plugging completed June 24, 1982  
 Reason for abandonment of well or producing formation Uneconomical for production

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow

Producing formation Niobrara Depth to top 1295' bottom 1332' T.D. 2013'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	364'	-0-
				4 1/2"	1482'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Pumped one sack of hulls, 102 sacks 50-50 Pozmix plus 4% gel plus 1% CaCl-2, 4 1/2"  
wiper plug and 10 sacks pumped to surface. Total 112 sacks. Cut 4 1/2" casing off  
and capped. Plug and abandon completed.

RECEIVED  
 STATE CORPORATION COMMISSION

JUL 2 1982

CONSERVATION DIVISION  
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services 17-2-82


STATE OF Kansas COUNTY OF Sedgwick, ss.

Charles E. Forrester (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) Charles E. Forrester  
Charles E. Forrester

209 E. William, (Address), KS 67202

1 day of July 19 82



Jacqueline Pierce  
 Jacqueline Pierce - Notary Public.

My Commission expires: 2-27-85

Zweygardt #1  
1980' FWL - 660' FNL  
Sec. 23-3S-41W  
Cheyenne Co., Kansas

15-023-20169-00-00

0' - 80'	Clay & Sand
80' - 1330'	Shale
1300' - 1355'	Niobrara
1355' - 2013'	Shale
2013' - TD	

RECEIVED  
STATE CORPORATION COMMISSION

APR 1 1982

CONSERVATION DIVISION  
Wichita, Kansas

4-14-82