

4-042004

1-26

API Number: 15-153-20,576 -00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

NW NW /4 SEC. 33, 03 S, 36 W
4720 feet from S section line
4520 feet from E section line

Operator license# 30606

Lease: Celia S. Well # F-5

Operator: Murfin Drilling Company

County: Rawlins 155.29

Address: 250 N. Water - #300
Wichita, Kansas 67202

Well total depth 4778 feet
Conductor Pipe: 0 inch @ 0 feet
Surface Pipe: 8 5/8 Inch 362 Feet
W/275 sxs.cmt.

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Swift Services, Inc. License# -

Address: Ness City, Kansas 67560

Company to plug at: Hour: 10:00 A.M. Day: 26 Month: January Year 1999

Plugging proposal received from: Jim Nowell

Company: Murfin Drilling Company Phone: -

Were: Ordered 225 sxs Swift M.D. Cement plus 18 sxs gel and 900# hulls.
5 1/2" casing set at 4771' w/200 sxs cement.
Perfs at 4698' - 4706'.
Anhy at 3100' - Dakota at 2300' - W.L.M. at 4710'.

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 1:15 P.M. Day: 26, Month: January, Year: 1999

Actual plugging report: Rigged up cementers to 5 1/2" casing. Squeezed 30 sxs cement with 400# hulls, followed with 10 sxs gel, followed with 35 sxs cement with 400# hulls, followed with 8 sxs gel, followed with 125 sxs cement with 100# hulls. Max. P.S.I. 200#. S.I.P. 200#. Rigged up to 8 5/8" S.P. Squeezed 35 sxs cement. Max. P.S.I. 400#. S.I.P. 400#.

Remarks: Perf by Perf Tech - Hays, Kansas 67601
Condition of casing(in hole): GOOD X BAD
Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC X, NO
Dakota plug: YES X, NO
Plugged through TUBING CASING X. Elevation: G.L.

I did [X] / did not [] observe the plugging.

Dennis L. Hamel
(agent)

RECEIVED Form CP-2/3
STATE CORPORATION COMMISSION

FEB - 5 1999
2-5-99

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 2-9-99

INV. NO. 60619