

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-01021-00-01  
Spot: E2NWSE Sec/Twnshp/Rge: 35-29S-7W  
2089 feet from S Section Line, 1752 feet from E Section Line  
Lease Name: ELMER HIBBS Well #: 4  
County: KINGMAN Total Vertical Depth: 4164 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

CIBP Size: feet: 3950 10 SX CMT  
PROD Size: 5.5 feet: 4163 75 SX CMT  
SURF Size: 8.624 feet: 251 200 SX CMT

*\$135<sup>33</sup>*

Well Type: SWD UIC Docket No: D21863.0 Date/Time to Plug: 08/18/2004 8:00 AM

Plug Co. License No.: 32938 Plug Co. Name: NORTH FORK WELL SERVICE LLC

Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: 8/17/04 STEVE VANGEISEN: 50 SX CLAS A 3% CC, BTM PLUG @ 3570', PERF BOM SALT SECTION - 1250'. 35 SX CLASS A 3% CC. SQZ IN LEAVE 50' INCAG. PERF TOP OF SALT 700', 35 SX CLASS A 3% CC SQZ IN LEAVE 50' IN CSG. CIRC. CMT UP 8-5/8 AND 5-1/2 ANNULUS AND FELL INSIDE.

**RECEIVED  
KCC DISTRICT #2  
AUG 30 2004**

Plugging Proposal Received By: STEVE VANGIESON

Witness Type: COMPLETE (100%)

**WICHITA, KS**

Date/Time Plugging Completed: 08/18/2004 5:30 PM

KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

Could not mill out packer. Ran tubing to 3536' and spotted 50 sacks of cement. Top of cement 3410'. Perforated at 1300' and squeezed 35 sacks of cement. Top of cement 1220'. Perforated at 650' and squeezed 35 sacks of cement. Top of cement 560'. Perforated at 300' and circulated cement to surface.

Common cement in squeeze.

60/40 posmix with 4% gel.

**Perfs:**

Top	Bot	Thru	Comments
4133	4142		
4125	4130		
4107	4117		
3700	3702		
3570	3594		


**RECEIVED  
SEP 10 2004  
KCC WICHITA**

Remarks: UNITED CEMENT #5398

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

**INVOICED**

DATE 9-10-04

INV. NO. 2005060522