

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-067-00501-00-00  
Spot: NE Sec/Twnshp/Rge: 14-30S-35W  
2540 feet from N Section Line, 2540 feet from E Section Line  
Lease Name: LIGHTY RAY Well #: 2-14  
County: GRANT Total Vertical Depth: 2728 feet

Operator License No.: 4824  
Op Name: PIONEER NATURAL RESOURCES USA.  
Address: 5205 N. O'CONNOR BLVD.  
IRVING, TX 75039

CIBP Size: feet: 2450 WITH 20 SX CMT  
PROD Size: 7 feet: 2512 WITH 175 SX CMT  
SURF Size: 10.75 feet: 560 WITH 100 SX CMT

# 88 66

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/01/2004 3:30 PM  
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.  
Proposal Rcvd. from: DAVID HIGGINS Company: PIONEER NATURAL RESOURCES Phone: (972) 444-9001

Proposed Plugging Method: CIBP @ 2450' WITH 20 SX CMT. PLUG AT 575' WITH 65 SX CMT. PLUG AT 300' WITH 30 SX CMT. PLUG AT 40' WITH 15 SX CMT. IF PIPE COMES LOOSE AT 1600'+, PUMP 30 SX CMT.

Plugging Proposal Received By: JIM HOLLAND Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/02/2004 12:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

SET CIBP @ 2450' WITH 20 SX CMT ON TOP. SHOOT 7" OFF AT 1033'. 1ST PLUG PULL OUT OF HOLE TO 575'. LOAD HOLE & PUMP 65 SX CMT. GOOD CIRCULATION. 2ND PLUG PULL OUT OF HOLE WITH 7" TO 300'. SDON. LOAD HOLE & PUMP 25 SX CMT AT 300'. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE WITH 7" TO 30'. LOAD HOLE & PUMP 15 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
2676	2728		SLOTTED LINER
2489	2694		SLOTTED LINER

RECEIVED  
SEP 10 2004  
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 1033' OF 7" CASING.

Plugged through: CSG

District: 01



Signed

Jim Holland (TECHNICIAN)

INVOICED

DATE 9-10-04

INV. NO. 2005010520

Form CP 2/3