

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19489-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 29-26S-7E
3630 feet from S Section Line, 2310 feet from E Section Line
Lease Name: GUENTHER Well #: A3
County: BUTLER Total Vertical Depth: 2758 feet

Operator License No.: 5387
Op Name: BUCKEYE CORP., AZTEC OIL CO. DIVI
Address: PO BOX 1020
EL DORADO, KS 67042

PROD Size: 5.5 feet: 2730 30 SX CMT
SURF Size: 7 feet: 2748 30 SX CMT

\$ 89⁶⁴

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/06/2004 2:30 PM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. D/B/A BRADEN PETROLEUM & WELL PLUGGING
Proposal Rcvd. from: JIM BRADEN Company: BRADEN PETROLEUM & WELL PL Phone: (316) 438-2856

Proposed Plugging Method: Open Hole 2748'-2758'.
Sand back to 2700' & 10 sxs; leave 2 jts of 7" in hole; circ cmt from 250'-0'.

RECEIVED
KCC DISTRICT #2
AUG 18 2004
WICHITA, KS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 08/06/2004 2:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The open hole was filled with sand to 2700' and capped with 10 sacks of cement. The 5-1/2" casing was recovered from 1690' and pulled from wellbore. The 7" casing was recovered from 275' and pulled to 60'. Tubing was run to 250' and circulated to surface. Left 2 joints of 7" in top of hole cemented in.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
2748	2758		

RECEIVED
SEP 10 2004
KCC WICHITA

Remarks: ALLIED #4422

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

INVOICED
DATE 9-10-04
INV. NO. 2005060.515