

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-20418-00-00  
Spot: N2NE Sec/Twnshp/Rge: 5-21S-19W  
660 feet from N Section Line, 1320 feet from E Section Line  
Lease Name: SMITH C Well #: 1  
County: PAWNEE Total Vertical Depth: 4324 feet

Operator License No.: 5088  
Op Name: DARRAH, JOHN JAY, JR.  
Address: 225 NORTH MARKET, STE 300  
WICHITA, KS 67202

CIBP Size: feet: 4240 WITH 2 SX CMT  
PROD Size: 4.5 feet: 4297 WITH 125 SX CMT  
SURF Size: 8.625 feet: 386 WITH 225 SX CMT

\$140<sup>53</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/03/2004 11:00 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: TED Company: SWIFT SERVICES, INC. Phone: (785) 798-2300

Proposed Plugging Method: SET CIBP @ PERFORATE AT 600'. PUMP 80 SX CMT OVER CASING VOLUME. 150 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/03/2004 12:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CIBP SET AT 4240' WITH 2 SX CMT. PERFORATED AT 600' & PUMPED 155 SX CMT. DID NOT CIRCULATE. MAXIMUM PRESSURE 800#. SHUT IN PRESSURE 400#. TIED ONTO BACKSIDE & PUMPED 20 SX CMT. PRESSURED TO 500# & HELD.

Perfs:


Top	Bot	Thru	Comments
4297	4324	OH	

RECEIVED  
SEP 10 2004  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

*Michael J. Maier*  
(TECHNICIAN)

INVOICED

DATE

9-10-04

INV. NO.

2005060516

Form CS-24