

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-20199-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 16-19S-10W
4950 feet from S Section Line, 4950 feet from E Section Line
Lease Name: OBERLE Well #: 1-V
County: RICE Total Vertical Depth: 3343 feet

Operator License No.: 3208
Op Name: K & N PETROLEUM, INC.
Address: 513 W. 6TH ST
ELLINWOOD, KS 67526

CIBP Size: feet: 3338
PROD Size: 5.5 feet: 3338 125 SX
SURF Size: 8.625 feet: 216 260 SX

\$108⁶⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/24/2004 9:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: EDWARDS S NEMNICH Company: K & N PETROLEUM, INC. Phone: (316) 215-1539

Proposed
Plugging
Method:

Sand to 3000' w/ 5 sxs; 1250' w/ 35 sxs & 100 lbs hulls; 900' w/ 35 sxs & 100 lbs hulls; 290' - 0'.

**RECEIVED
KCC DISTRICT #2
AUG 30 2004
WICHITA, KS**

Plugging Proposal Received By: DOUG LOUIS WitnessType: NONE
Date/Time Plugging Completed: 06/25/2004 2:00 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Sanded bottom to 3000' and 5 sacks of common cement. Cut casing off at 1550'. Pulled to 1250' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled to 900' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled to 290' and circulated cement to surface.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
3338			Arbuckle OH
3178	3180		
3066	3074		

**RECEIVED
SEP 10 2004
KCC WICHITA**

Remarks: COPELAND

Plugged through: CSG

District: 02

Signed

Jack Luthi

(TECHNICIAN)

INVOICED
DATE 9-10-04
INV. NO. 2005060518