

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-20181-00-00  
Spot: NWNE Sec/Twnshp/Rge: 17-19S-10W  
390 feet from N Section Line, 960 feet from E Section Line  
Lease Name: MANSZ Well #: 2-D  
County: RICE Total Vertical Depth: 3350 feet

Operator License No.: 3208  
Op Name: K & N PETROLEUM, INC.  
Address: 513 W. 6TH ST  
ELLINWOOD, KS 67526

CIBP Size: feet: 3062  
PROD Size: 5.5 feet: 3346 125 SX  
SURF Size: 8.625 feet: 225 200 SX

\$ 108<sup>88</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/06/2004 8:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: EDWARDS S. NEMNICH Company: \_\_\_\_\_ Phone: (620) 587-3361

Proposed Plugging Method: Bridge plug 3062'; 1250' w/ 35 sxs; 900' w/ 35 sxs; 275' - 0'.

RECEIVED  
KCC DISTRICT #2  
AUG 30 2004  
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI Witness Type: NONE  
Date/Time Plugging Completed: 07/08/2004 5:00 PM KCC Agent: JACK LUTHI

Actual Plugging Report:

Sanded bottom at 2955' with 70 lbs of sand and 5 sacks of cement. Cut casing off at 1300'. Pulled to 1250' and pumped 35 sacks of cement. Pulled to 900' and pumped 35 sacks of cement. Pulled to 275' and circulated cement to surface.

60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
3023	3026		
3006	3010		

RECEIVED  
SEP 10 2004  
KCC WICHITA  
RECEIVED  
SEP 17 2004  
KCC WICHITA

Remarks: COPELAND #23556

Plugged through: CSG

District: 02

Signed

Jack Luthi  
(TECHNICIAN)

INVOICED  
DATE 9-10-04  
INV. NO. 2005060518