

9-25-87

To: 6 030959  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 023-20,147-00-00

SE NW SE, SEC. 13, T 03 S, R 39 W&E

1650 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 04526

Lease Name Witham Well # 1-13

Operator: Barfield Oil Corp.  
Name & Address: 1512 Larimer Street Suite 400  
Denver, Colorado 80202

County Cheyenne 19.37  
Well Total Depth 1519 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 7" feet 301

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor B. J. Titan License Number \_\_\_\_\_

Address Oakley, Kansas

Company to plug at: Hour: AM Day: 25 Month: Sept Year: 19 87

Plugging proposal received from Gary Andrews

(company name) Barfield (phone) \_\_\_\_\_

were: 7" set at 301' w/61 sks. 4 1/2" set at 1519' w/50 sks. PBTD 1481'.

Perf 1368' - 94'. Order 60 sks 65/35 Pozmix 10% Gel 2% Dical Cement Blend.  
400# Hulls. B. J. Titan Cement Company. Idalia Water Truck.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:00AM Day: 25 Month: Sept Year: 1987

ACTUAL PLUGGING REPORT Squeeze 4 1/2" casing w/40 sks Cement Blend with 400# Hulls mixed in.

Max Psi 1000# Close in Psi 800#. Squeeze backside w/20 sks Cement Blend.

Max Psi 200# Close in 200#. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 23 1987  
10-23-87

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 10-26-87

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

INV. NO. 18648 OCT 29 1987 DEC 03 1987