

6 031381

6-12

023-20,282 -0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- _____
SE NW NE, SEC. 1, T 3 S, R 38 W&E

4290 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8793

Lease Name Burr Well # 1-D

Operator: James Dillie

County Cheyenne 159.58

Name & Address 4469 So. Winona Court

Well Total Depth 4910 feet

Denver, Colorado 80236

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 365

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A xx

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling License Number _____

Address Wichita, Ks.

Company to plug at: Hour: _____ PM Day: 12 Month: June Year: 19 90

Plugging proposal received from Steve Carlton

(company name) Murfin (phone) _____

were: 8 5/8 set at 365 w/210 sks. Cir hole with no less than 36 vis mud w/ no loss or gain in fluid. Balance cement plugs w/mud.

Order 190 sks 60/40 pozpoz 6% gel 35 cc, 8 5/8 w.p. B. J. Titan Cement Co.

Water Well plugged by Woofter.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None xx

Operations Completed: Hour: 8:30PM Day: 12 Month: June Year: 19 90

ACTUAL PLUGGING REPORT Spot cement plugs w/drill pipe at 3175' w/25 sks.

2350 w/100 sks and hulls.
400 w/40 sks

40 w/10 sks

15 sks in rathole w/joint of pipe.

RECEIVED
STATE CORPORATION COMMISSION

JUL 13 1990

CONSERVATION DIVISION
Wichita, Kansas

6-13-90

Remarks: Elev. 2100 Anhy 3173 - 3200.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-24-90

INV. NO. 28704

6-12-90

John S.

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow