

6 030708

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-023-20,244-00-00

SESWNW SEC. 12, T. 3 S, R. 37 W

2970 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4528

Lease Name BRINEY Well # 12-26

Operator: PAUL PRIJATEL

County CHEYENNE 158.2P

Name & Address 201 W. 8TH ST. STE 450

Well Total Depth 4870 feet

PUEBLO COLORADO

Conductor Pipe: Size _____ feet

B1003

Surface Casing: Size 8 3/8 feet 410'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor GOLDEN EAGLE DRLG. INC. License Number 8682

Address MCCOOK, NEBRASKA

Company to plug at: Hour: AM Day: 27 Month: 2 Year: 19 86

Plugging proposal received from DAVE

(company name) GOLDEN EAGLE (phone) _____

were: 8 3/8 @ 410' w/270SX. WITH HOLE FULL OF 36UIS. MUD OR MORE
AND NO LOSS OR GAIN OF FLUID SPOT CEMENT PLUGS WITH DRILL PIPE
ORDER 200 SX. 60/40POZ GEL. 3%CC. NO W.P. HALLIBURTON
SERVICES

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:30AM Day: 27 Month: 2 Year: 19 86

ACTUAL PLUGGING REPORT SPOT D.P. @ 3275' DISPLACE 25 SX. CNT. MIX.

LAYDOWN D.P. TO 2500' DISPLACE 100 SX. CNT. MIX. + 15X. HULLS LAYDOWN
D.P. TO 460' DISPLACE 40 SX. CNT. MIX. LAYDOWN D.P. ESTABLISH
MUD LEVEL 40' BELOW BASE OF CELLAR - OPEN END 10 SX. CNT. MIX.
FROM 40' TO BASE OF CELLAR. DISPLACE 15 SX. IN R.H. AND 10 SX IN M.H.
PLUG COMPLETE

Remarks: ELEV. 3397 ANHY 3255-3291

STATE CORPORATION COMMISSION

INVOICED

(If additional description is necessary, use BACK of this report) APR 28 1986 4-28-86

I (did / did not) observe this plugging.

CONSERVATION DIVISION
Wichita, Kansas

DATE APR 29 1986

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. 13596