

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-023-20234-00-00
Spot: CSWNE Sec/Twnshp/Rge: 12-3S-37W
3300 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: ROESENER Well Number: 1
County: CHEYENNE Total Vertical Depth: 4849 feet

Operator License No.: 3602
Op Name: PHILPOTT OIL & GAS CO INC
Address: PO BOX 450 408 MAIN
ATWOOD, KS 67730

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 387 w/250 sxs cmt \$
Production: Size 4.5 feet: 4850 w/325 sxs cmt 157.59
Liner: Size feet:

Well Type: OIL UIC Docket No.: Date/Time to Plug: 05/14/2001 4:00 PM

Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.

Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 12 yards Redi-Mix - 6 sxs common cement - 3000# sand - 40 gallons water/yard.

Plugging Proposal Received By: CARL GOODROW

Witness Type: Plugging Operations Partially Witnessed

Date/Time Plugging Completed: 05/14/2001 5:00 PM

KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 387' w/250 sxs. 4 1/2" set at 4850' w/325 sxs.
Prod Perfs 4712' - 4718'; 4788' - 4791'.
PBTD 4816'. Exempt area.
Fluid level low.
Three shots recovered 2000' of 4 1/2".
Filled hole with 12 yards Redi-Mix.
Plug complete.

INVOICED
DATE 5-31-01
SER. NO. 2001061867

RECEIVED
KANSAS CORPORATION COMMISSION
MAY 31 2001
5-31-2001
CONSERVATION DIVISION

Remarks:

Plugged through: CSG


District: 04

Signed Carl Goodrow
(TECHNICIAN)

MAY 16 2001

REPLACEMENT CARD

MAGNUS OIL & GAS
 1002 FOURTH ST.
 ARAPAHOE, NE 68922
 CONTR GOLDEN EAGLE DRILLING CTY: CHEYENNE
 GEOL PAUL PRIJATEL FIELD WC(6-1/2 SE OF KEN
 ABD)
 ELV 3391 KB SPD 5/30/85 CARD ISSUED 12/26/85 IP P 22 BO & .5 BWPD
3386 GL DRLG COMP 6/8/85 MARM(FT SC) 4712-4718
 API 15-023-20,234



SMP	Tops	Depth/Datum
DAK	2130+1261
SC	3239 152
B/SC	3273+ 118
OREAD	4222- 831
LANS	4314- 923
BKC	4600-1209
FT SC	4714-1323
CHER SH	4736-1345
RTD	4849-1458

8 5/8 " 388 / 250SX, 4 1/2 " 4849 / 325SX
 NO CORES
 DST (1) 4693-4726 (FT SC) / 30-60-30-60, REC 10' OCM, 360'
 OIL SPTD M, SIP 1284-1264#, FP 100-120 / 160-160#
 MICT - CO, PF (CHER) 4788-4791, W / 2 SPF, AC 300 GAL (15%
 MCA), PFS WOULD NOT BREAK DWN AT 3000 PSI, PF (FT SC)
 4712-4718, W / 2 SPF, AC 600 GAL (15% MCA) & 500 GAL (15%
 PAD), SWB LD, RE-AC 2000 GAL (GEL PAD) & 6000 GAL (15%
 SGA) & 2000 GAL OVERFLUSH; SO, SET 2 3/8 " TBG AT 4778,
 POP, P 22 BO & .5 BWPD (GR 39%), 7/1/85

INFO RELEASED: 7/17/86 - WAS OIL WELL - TIGHT HOLE

COPYRIGHT 1985
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

INDEXED