

6 070407

API NUMBER 15-023-20, 240-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C-SE-NW, SEC. 9, T. 2 S, R. 27 W
3300 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9477
Operator: Central Operating Inc
Name & Address: 515 Union Blvd #203
Lakewood Colorado
Jim Gill 80228

Lease Name Rogers Well # 6-9
County Cheyenne 159.09
Well Total Depth 4895 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8" feet 434

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated tag

Plugging Contractor Murphy Dalg Co License Number 6023

Address Wichita, Kansas 67202

Company to plug at: Hour: 8:45 AM Day: 20th Month: Oct Year: 1985

Plugging proposal received from Steve Carlton

(company name) Murphy Dalg Co Inc (phone) 303-985-7209

were: 8 5/8" 434 ft SP. CUC 1/205, 3/4" 60/140 Formix 3% ca-cl By Halliburton
Order 200 3/4" 60/140 Formix 6% ca-cl - 1 1/2" cells and 8 5/8" Plug
spot with Drill Stem, Recondition Well (Pressure) mud between all plugs
No buckble, no circulation problems, mud condition
weight 9 - viscosity 47.

Plugging Proposal Received by Murphy Dalg
DDIC (TECHNICIAN)

Plugging Operations attended by Agent? All _____ Part _____ None

Operations Completed: Hour: 8:45 AM Day: 20th Month: Oct Year: 1985

ACTUAL PLUGGING REPORT Ordered 200 3/4" 60/140 Formix 6% ca-cl - 1 1/2" cells

and 8 5/8" Plug, spotted with Drill Stem, Reconditioned Well,
Heavy mud between all plugs.

1st Plug @ 2300 ft 1/205, 2nd Plug @ 2170 ft 1/100 cells
3rd Plug @ 440 ft 1/205, 4th Plug @ 40 ft 1/10 cells
10" In Pat able (circulate), Plug @ 40 ft 1/10 cells.

Remarks: Cemented by Halliburton. Cont

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE NOV 12 1985

INV. NO. 10946

RECEIVED
NOV 4 1985
CONSERVATION DIVISION
Wichita, Kansas

Signed Murphy Dalg
DDIC (TECHNICIAN)