

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-067-20132 00-00

LEASE NAME Stubbs A

WELL NUMBER 2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1320 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 35 TWP. 28 RGE. 37 (E) or (W)

COUNTY Grant

Date Well Completed 3-30-72

Plugging Commenced 8-18-04

Plugging Completed 8-18-04

LEASE OPERATOR Oxy USA, Inc.

ADDRESS 1701 N. Kansas P.O. Box 2528 Liberal, KS. 67905

PHONE (620) 629-4200 OPERATORS LICENSE NO. 5447

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-18-04 (date)

by Mike Meyer (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation Council Grove Depth to Top 2705 Bottom 2766 T.D. 2877

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 3/8	689	-
				5 1/2	2877	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Mixed 300 lb. hulls & 25 sx cmt. to plug perfs from 2705 to 2505, pumped mud spacer to 1700, mixed 25 sx plug from 1700 to 1500, mud spacer to 700, mixed 77 sx from 700 to 0. Cmt fell 80 ft. Left overnight. Mixed 10 sx 80-0. Cut off 8 3/8 & 5 1/2 & capped 8 3/8 3 ft. below G.L.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oxy USA Inc.


STATE OF Kansas COUNTY OF Seward, ss.

Kenny Andrews (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) Kenny Andrews

(Address) PO Box 2528 Liberal, KS. 67905

SUBSCRIBED AND SWORN TO before me this 10th day of September, 19 2004



My Commission Expires: November 8, 2006 Notary Public