


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-023-30037-00-00
WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Cheyenne County. Sec. 13 Twp. 3S Rge. (E) 42 (W)

Location as "NE/CNW/SW" or footage from lines SE/4 NW/4
Lease Owner Sun Oil Company
Lease Name Walz Well No. 1
Office Address Box 1348, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dryhole
Date well completed 7-15 19 59
Application for plugging filed Yes 19
Application for plugging approved Yes 19
Plugging commenced 7-24 19 59
Plugging completed 7-27 19 59
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4546 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	320.43	None
				4 1/2"	4562.24	2459'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into TD 4546'.
Plugging started 7-24-59. Finished 7-27-59.
Sanded to 4510' and dumped 3 sacks of cement. Worked and shot pipe.
Shot 4 1/2" csg. at 2459'. Pulled pipe out of hole and plugged well as follows:
Mudded to 324'. Set rock bridge and dumped 25 sacks of cement. Filled hole with mud to 40'. Set rock bridge and mixed 10 sacks of cement for cap on well. Well Completed.

RECEIVED
STATE CORPORATION COMMISSION

AUG 26 1959

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas 8-26-59

STATE OF OKLAHOMA, COUNTY OF TULSA, ss.
J. H. Allen (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. H. Allen
J. H. Allen, Asst. Prod. Supt.
Box 1348, Tulsa, Oklahoma (Address)

SUBSCRIBED AND SWORN TO before me this 25th day of Aug, 19 59

My commission expires March 3, 1960
James E. McPartey Notary Public.

24-7368-5 3-53-20M

PLUGGING
FILE SEC 13 T 3 R 42 W
BOOK PAGE 63 LINE 36

R
 DRILLERS' LOG

SUN OIL COMPANY
 Walz No. 1
 SE NW

Sec. 13, Township 3S, Rge. 42W
 Cheyenne County, Kansas

15-023-30037-00-00

RECEIVED
 STATE CORPORATION COMMISSION

DEC 1 0 1959
 CONSERVATION DIVISION
 Wichita, Kansas

12-10-59

FORMATION

	<u>FROM</u>	<u>TO</u>
Shale	0'	1572'
Shaly sand & sdy. sh	1752'	2120'
Sand & shale	2120'	2315'
Sha&e	2315'	2520'
Sand, sh., ls. strks	2520'	2694'
Shale	2694'	2830'
Sh. w/ls & sd strks	2830'	3090'
Shale w/ls strks	3099'	3278'
Lime	3278'	3510'
Lime, sand, shale	3510'	3670'
Sdy. shale & shale	3670'	3880'
Sand	3880'	3922'
Sdy. shale	3922'	3973'
Sand	3973'	3994'
Shale and sand	3994'	4040'
Lime & shale	4040'	4258'
Lime	4258'	4275'
Shale & lime	4275'	4306'
Lime and shale	4306'	4446'
Lime	4446'	4476'
Shale & lime	4476'	4514'
Lime	4514'	4544'
Shale & lime	4544'	4560'

Drilling Commenced 6-24-59
 Drilling Completed 7-4-59
 Dry & Abandoned 7-13-59

Elev. DF 3636'; GL 3630½"

Casing Record:

8-5/8" 24# J55 at 332' cemented to GL 300 sax.

4½" 9.5# & 11.6# J55 at 4559.5', cemented w/400 sax.

Perforating Record:

4514-4523' & swabbed 10 bbls. salt water hourly, cutting 10% black oil.

Hole plugged 7-27-59

T.D.

Electric Log Tops:

Topeka Lime	4306'
Lansing Lime	4446'

I hereby certify that the foregoing is a true and correct copy of the Walz No. 1 well log as recorded on the books of Sun Oil Company, Tulsa Oklahoma.

J. H. Allen

 J. H. Allen

STATE OF OKLAHOMA)
) SS
 COUNTY OF TULSA)

Subscribed and sworn to before me this 3rd Day of December, 1959.

Dorothy Little

 Notary Public

My Commission Expires:

July 25, 1962