


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Cheyenne County. Sec. 9 Twp. 3S Rge. (E) 42 (W)

Location as "NE/CNW%SW%" or footage from lines SE SE SE
Lease Owner Sun Oil Company
Lease Name Rueb Well No. 1
Office Address Box 1348, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dryhole
Date well completed _____ 19____
Application for plugging filed Yes _____ 19____
Application for plugging approved Yes _____ 19____
Plugging commenced _____ 7-19 19 59
Plugging completed _____ 7-23 19 59
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5450 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	313.04	None
				4 1/2"	4705.20	2622'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into TD 4567'.
Plugging started 7-19-59. Finished 7-23-59
Sanded to 4465' and dumped 3 sacks of cement. Worked and shot pipe.
Shot 4 1/2" csg. at 2622'. Pulled pipe out of hole and plugged well as follows:
Mudded to 300'. Set rock bridge and dumped 25 sacks of cement. Filled hole with mud to 40'. Set rock bridge and mixed 10 sacks of cement for cap on well. Well Completed.

RECEIVED
STATE CORPORATION COMMISSION

AUG 26 1959

CONSERVATION DIVISION
Wichita, Kansas

8-26-59

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Co.
Address Box 221, Great Bend, Kansas

STATE OF OKLAHOMA, COUNTY OF TULSA, ss.
J. H. Allen (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. H. Allen
J. H. Allen, Asst. Prod. Supt.
Box 1348, Tulsa, Oklahoma
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of Aug, 1959

My commission expires March 3, 1960

James E. W. [Signature]
Notary Public.

PLUGGING
FILE SEC 9 T. 3 R. 42
BOOK PAGE 63 LINE 29

15-023-00021-00-00

P DRILLERS" LOG

SUN OIL COMPANY
Rueb No. 1
SE SE
Sec. 9, Twp. 3S, Rge. 42W
Cheyenne County, Kansas

RECEIVED
STATE CORPORATION COMMISSION

DEC 10 1959

CONSERVATION DIVISION
Wichita, Kansas

12-10-59

<u>Formation</u>	<u>From</u>	<u>To</u>
Sand & shale	0	340
Shale	340	1550
Sand, shaly sand	1550	2140
Shale	2140	2335
Lime	2335	2368
Shale w/thin ls strks	2368	3320
Lime w/sh strks	3320	3790
Strks ls & sh	3790	4404
Strks ls & sh	4404	4795
Sand	4795	4820
Shale & ls	4820	5244
Shale	5244	5303
Lime & shale	5303	5368
Lime	5368	5450
		T.D.

Drilling Commenced	6-2-59
Drilling Completed	6-18-59
Dry & Abandoned	7-15-59

Casing Record:

8-5/8" at 325' w/300 sax cement
4 1/2" at 4714' w/300 sax cement

Perforating Record:

4608-13' swabbed 11 bbls. fluid
8 hrs., 25% oil, 75% salt water.
Squeezed w/200 sax cement.
Perf. 4618-41', swab .83 bbls.
salt water per hr.
Squeezed w/75 sax cement.
Perf. 4469-4476' and swabbed 18
bbls. salt water in 5 hrs.

Electric Log Tops:

Topeka	4404'
Lansing	4544'
Morrow Shale	5244'
Mississippi	5368'

I hereby certify that the foregoing is a true and correct copy of the Rueb No. 1 well log as recorded on the books of Sun Oil Company, Tulsa Oklahoma

J. H. Allen

J. H. Allen

STATE OF OKLAHOMA)
) SS
COUNTY OF TULSA)

Subscribed and sworn to before me this 3rd day of December, 1959.

Dorothy Little

Notary Public

My Commission Expires:

July 25, 1962