

3 055812

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-001-~~DRILLED~~ 1961 <sup>01871-00-00</sup>  
SWNWSWNE Sec/Twp/Rge 14-25-19E  
3390 feet from south section line  
2440 feet from east section line <sup>63500</sup>

TECHNICIAN'S PLUGGING REPORT

Operator License # 6137

Lease/Well# MCENDREE # 2

Operator: ENSMINGER OIL

County ALLEN

Name & 1446-3000 ST

Well Total Depth 855 feet

Address MORAN, KS 66755

Production Pipe: 2 Size Feet 840

AB oil well XXXX Gas Well \_\_\_\_\_ SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Surface Casing: 8 5/8 Size Feet 20

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: CO TOOLS Lic. # \_\_\_\_\_

Address: \_\_\_\_\_

Company to plug at: Hour: 10:00 Day: \_\_\_\_\_ 3 Month: 9 2004

Plugging proposal received from: DAVE KIMZEY

Company Name: ENSMINGER OIL Phone: 620-237-4320

Were: \_\_\_\_\_

840' OF 2" SET ON RAG PACKER WITH SOME CEMENT

PUMP 2" FULL WITH CEMENT

FILL WITH CEMENT FROM 250' TO SURFACE OUTSIDE 2" PIPE

Plugging Proposal Received by: T J WELSH

Plugging attended by Agent: All \_\_\_\_\_ Part XXXX <sup>TECHNICIAN</sup> None \_\_\_\_\_

Operations Completed: Hour: 12:00 PM Day: \_\_\_\_\_ 3 Month: 9 2004

Actual Plugging Report: \_\_\_\_\_

RAN 855 FT OF 1" PIPE INSIDE 2" PIPE PUMP 60 SX CEMENT TO SURFACE

RAN 250 FT OF 1" PIPE OUTSIDE 2" PIPE PUMP GEL AND COTTON SEED HULLS

UNTIL CIRCULATION APPEARED PUMP 30 SX CEMENT TO SURFACE

RECEIVED

SEP 13 2004

KCC WICHITA

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed: Thomas J Welsh  
TECHNICIAN

INVOICED

DATE 9-16-04  
INV. NO. 2005060534

*[Handwritten mark]*